

NOTICE OF MEETING
VILLAGE OF FOX POINT
BUILDING BOARD

Schwemer Hall
7200 North Santa Monica Blvd.
Fox Point, WI 53217

Wednesday
September 10, 2024
5:00 P.M.

Join Zoom Meeting

<https://us02web.zoom.us/j/88643620031>

Meeting ID: 886 4362 0031

Dial by your location: 312.626.6799

AGENDA

1. Roll call of board members and quorum confirmation.
2. Discussion, corrections, and approval of the minutes of the August 14, 2024 Building Board meeting.
3. Ellie DeLia, 7633 N Links Way, proposed sunroom.
4. Brian Wolff, 7528 N Links Way, proposed garage addition.
5. Lisa Friedel, 7402 N Crossway Rd, proposed window size change.
6. Laurie Bergum, 7630 N Boyd Way, proposed second story addition.
7. Linda Tredupp, 8025 N Whitney Rd, proposed deck.
8. Adjourn.

Posted and published September 9, 2024 10:30 AM

PLEASE NOTE: Upon reasonable notice, efforts will be made to accommodate the needs of disabled individuals through sign language interpreters or other auxiliary aids. For additional information or to request these services, contact the Village Clerk at 414-351-8900. It is possible that members of, and possibly a quorum of members of, other governmental bodies of the municipality may be in attendance at the above stated meeting to gather information; no action will be taken by any governmental body at the above stated meeting other than the governmental body specifically referred to above in this notice.

**VILLAGE OF FOX POINT
BUILDING BOARD MINUTES**

A meeting of the Building Board was held via Zoom, on Wednesday, August 14, 2024, at 5:00 pm. Those present included:

Justin Racinowski
William Feldman
Sharon Celek
Lucille Sells-Absent
Brian Tobiczkyk
Michael Rakow

Notice of the meeting was provided to the North Shore Now and to all others as required by State open meeting laws and posted on the official bulletin boards.

MINUTES

Motion was made by Sharon Celek to approve the minutes of July 10, 2024. Motion was seconded by William Feldman. Motion Caried.

AGENDA

1. [REDACTED], 1518 E Goodrich Ln, proposed bedroom & bathroom addition to 2nd floor. It was the consensus of the Building Board to approve as submitted.
2. Philip Lator, 7950 N Port Wash Rd, proposed sign. It was the consensus of the Building Board to approve as submitted.
3. Jaun Carlos Chang Shik, 803 E Bradley Rd, proposed roof mounted solar. It was the consensus of the Building Board to approve as submitted.
4. Susan LaBudde, 7439 N Fairchild Rd, proposed roof mounted solar. It was the consensus of the Building Board to approve as submitted.
5. David Sadoff, 7855 N Club Cir, proposed awning. It was the consensus of the Building Board to approve as submitted.
6. Greg Kauffmann, 8244 N Gray Log Ln, proposed window assemblies. It was the consensus of the Building Board to approve as submitted.
7. Elizabeth Casmer, 8566 N Regent Rd, proposed garage addition. It was the consensus of the Building Board to approve subject to the two gable end dormers on the front side, increase the window size by lowering the sills.

ADJOURN

Motion to adjourn Building Board was made by William Feldman. Motion seconded by Brian Tobiczkyk. Motion Caried. Building Board adjourned at 6:01 pm.

Respectfully Submitted,



Michael Rakow
Building Inspector
Village of Fox Point



VILLAGE OF FOX POINT
 7200 N Santa Monica Blvd
 Fox Point, WI 53217
 (414) 247-6622
 www.villageoffoxpoint.com

Permit Number:
 B- _____

OFFICE USE ONLY	
Issued Date	
Zoning	

BUILDING PERMIT

Job Address	7633 North Links Way	Building Type:	Residential <input checked="" type="checkbox"/> Commercial <input type="checkbox"/>
Description of Work	Replace existing sunroom with new sunroom on existing deck. Sunroom will be thermally isolated from the house. House door to remain. Replacing with same footprint as original		
Estimated Cost of Project \$	125,000.00		

Owner/Occupant		Ellie DeLia	
Business Name	Contact Name	Ellie DeLia	
Address	City/State/Zip	Fox Point WI 53217	
Phone	Email	elliedelia@gmail.com	

****Cautionary Statement required when homeowner is applying for permit****

Contractor			
Company Name	Great Day Improvements	Contact Name	Karuy Bell
Address	W41N9896 Fountain Blvd	City/State/Zip	Menomonie Falls WI 53051
Phone	440-817-0611	Email	cadpermits@greatdayimprovements.com
Dwelling Contractor #	DC-D12000102	Dwelling Contractor Qualifier #	DCQ-D12000077

Square Footage Under Construction				
1 st Floor	2 nd Floor	Basement	Addition	Garage
			206-	same as existing

Description	Rate	Amount
Project - Per \$1,000 of estimated cost	\$10.00	
Building Board	\$75.00	
Footing early start - \$230.00 one and two family; \$305.00 commercial		
Plan Review - \$275.00 one and two family; New Single Family Construction \$330.00 plus \$30.00/unit commercial		
State Seal	\$75.00	
Razing, Interior Demolition \$925.00 max/bld \$95.00 minimum plus	\$0.13/sqft	
Moving buildings \$250.00 plus	\$0.13/sqft	
Fuel tanks - Per 1,000 gallons	\$25.00	
Re-inspection	\$100.00	
Work started without permit	Double	
	Minimum Fee	\$70.00
Payable to: Village of Fox Point	Total Permit Fee	\$

Applicant Signature Karuy Bell Date 8-6-24
 Rev 01/22

ISSUED PERMITS are available on the Village website under **PERMITS & LICENSES**

VILLAGE OF FOX POINT
7200 N. SANTA MONICA BLVD
FOX POINT WI 53217

414-351-8900

Receipt No: 1.060663

Aug 21, 2024

7633 N Links Way

Previous Balance:	.00
LICENSES & PERMITS - BUILDING PLANS - FILING FEE	75.00
24-44440 BUILDING PLANS-FILING FEE	

Total:	75.00
--------	-------

CHECK	Check No: 72519	75.00
-------	-----------------	-------

Payor: GREAT DAY IMPROVEMENTS LLC

Total Applied:	75.00
----------------	-------

Change Tendered:	.00
------------------	-----

08/21/2024 2:04 PM



VILLAGE OF FOX POINT

7200 N Santa Monica Blvd
Fox Point, WI 53217
(414) 247-6622
www.villageoffoxpoint.com

BUILDING BOARD

Building Board typically meets on the second Wednesday of every month at 5:00 p.m. The application deadline is 12:00 p.m., two Fridays prior to the meeting. All applications must be complete and include the proper filing fee.

Building Board meetings will be held via Zoom. Building Board agenda with the Zoom address will be posted on the website under Agendas & Minutes.

Examples of projects that must appear before the Building Board: New Construction, Additions, Exterior Improvements, Detached Garage, Decks, Sheds > 100 sq. ft., Window Replacement, New Doors, Patio Doors, Pools, Signs, and Solar Systems.

Complete Building Board Applications must include:

- One set of drawings** to 1/4 inch scale on 24" x 36" maximum size sheets. These shall include all elevations, floor plans, foundation plan, and cross sections.
 - Elevation Drawings shall include all proposed elevations of the building, even if changes to the elevation are not proposed. This is to ensure consistency of all elevations. In cases where a building element may be skewed from another, it may be necessary to draw more than the four primary elevations of the building to clearly explain the intent of the design. All building elevations must be fully dimensioned to indicate heights above grade for all components. If the project is a building addition or remodeling, the original structure should be clearly illustrated as new building versus existing structure.
 - The complete existing elevation should be shown in all cases of additions and remodeling. All building materials must be identified and noted on each elevation drawing. This is to include, but not limited to, type and size of siding, type and size of masonry, window type size and material, roofing material, fascia, rakes, soffits, eaves, and flashing materials. It is recommended to bring material samples and colors.
 - Dimensioned floor plans shall include all floor plans of the proposed building. Each plan must include complete dimensions, and include room names for each space. In the case of an addition, each room shall be tagged either existing or new. In the case where there is a detached garage, a separate plan, fully dimensioned, for the garage must be included.
- Color photos** that includes all elevations of existing home and any accessory structures on the property.
- Survey** less than one year old **or** an accurate survey showing all existing buildings, decks, in-ground pools, hardscaping and any non-pervious paving, prepared by a certified surveyor registered by the State of Wisconsin. **Required for Additions, Accessory Structures, Decks, New Construction, In-ground Pools/Hot Tubs (and pads for above-ground hot tubs), and Solar Panels (Ground mount only).** This must include all property lines with distances bearings, North arrow, exact location of all existing and proposed buildings, parking areas, drives, public improvements, easements, and other key features of the site. Show distances from front, rear and side property lines.
- Site plan** include a North arrow and dimensions. **Required for Additions, Accessory Structures, Decks, New Construction, In-ground Pools/Hot Tubs, and Solar Panels (Ground mount only).** This document must include all property lines, utility and access easements, zoning setbacks, exact location of all existing and proposed buildings or additions including roof overhangs, all hard surfaced areas (parking areas, drives, patios, sidewalks, etc.), swimming pools, and other accessory structures.
- Open area** calculation required for Additions, Accessory Structures, Decks, New Construction, In-ground Pools/Hot Tubs, and Solar Panels (Ground mount only).
- One Electronic copy of entire Building Board packet** emailed to mrakow@villageoffoxpoint.com
- Completed Building Permit Application.**
- Building Board Fee \$75.00** payable to the Village of Fox Point.

A REPRESENTATIVE MUST ATTEND BUILDING BOARD MEETING





MINIMUM DESIGN LOADS: PER WISCONSIN SPS 320-325 / 2018 UDC / ASCE 7-05

NOTE: COMPONENTS HAVE BEEN CHECKED AGAINST DESIGN LOADS SHOWN & FOUND TO BE ACCEPTABLE STRUCTURALLY

DEAD LOADS:
1. ROOF: 6 PSF
2. WALLS: 6 PSF

SNOW LOADS: GROUND SNOW LOAD 30 PSF

WIND PRESSURE: 20 PSF

LIVE LOADS: ROOF: 30 PSF

DEFLECTION LIMITS:
1. ROOF: L/120
2. WALLS: L/175

THIS THERMALLY ISOLATED SUNROOM IS UNCONDITIONED AND NOT HABITABLE

NOTE: THE P.E. STAMP ON THESE DRAWINGS ADDRESS ONLY THE GDI MANUFACTURED COMPONENTS, & THE ANCHORAGE OF THESE COMPONENTS TO THE EXISTING STRUCTURE.

NOTES:

1. ALLVIEW (CA5) SUNROOM; WHITE IN COLOR
2. CONSTRUCT SUNROOM ON EXISTING DECK
3. ELECTRICAL BY GDI
4. CONCRETE
 - A) CONCRETE WORK SHALL CONFORM TO ALL REQUIREMENTS OF ACI 301 SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS.
 - B) ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI AT 28 DAYS. EXTERIOR FLOORS AND EXPOSED CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4500 PSI AND 5% TO 7% AIR ENTRAINMENT.
5. WOOD
 - A) MATERIALS - FRAMING LUMBER
 - i) WOOD POSTS: NO. 2 GRADE (OR BETTER) SOUTHERN PINE OR DOUGLAS FIR
 - ii) 2x8, 2x10, 2x12 NO. 2 GRADE (OR BETTER) SOUTHERN PINE OR DOUGLAS FIR
 - B) WOOD MEMBERS SHALL BE PRESSURE-TREATED FOR THE FOLLOWING CONDITIONS:
 - i) IN DIRECT CONTACT WITH THE GROUND
 - ii) SILLS OR PLATES ON CONCRETE WITHIN 8" OF FINISHED GRADE
 - iii) JOISTS AND SUBFLOORS WITHIN 18" OF FINISH GRADE AND BEAMS WITHIN 12" OF FINISH GRADE
 - iv) EXPOSED EXTERIOR DECKS
 - C) FASTENERS

ALL FASTENERS AND HARDWARE USED TO CONNECT TO PRESSURE TREATED WOOD MEMBERS SHALL EITHER BE 304 OR 316 STAINLESS STEEL, OR HOT DIPPED GALVANIZED PER ASTM-A653 COATING DESIGNATION G-185 AND ASTM-A153
6. STRUCTURAL ALUMINUM
 - A) ALL EXTRUSIONS SHALL BE COMMERCIAL GRADE ALUMINUM SUPPLIED BY GREAT DAY IMPROVEMENTS, LLC.
 - B) ROOF PANELS SHALL BE 3" OR 6" THICK SUPER FOAM ROOF PANELS FACED WITH A 0.024" ALUMINUM SKIN TOP AND BOTTOM.
7. THIS SUNROOM IS CONSIDERED AS NON-CONDITIONED SPACE, EXEMPT FROM ENERGY REQUIREMENTS

GREAT DAY IMPROVEMENTS
PATIO ENCLOSURES, MILWAUKEE
De LIA RESIDENCE

SHEET #	DESCRIPTION
1	COVER
2	ELEVATION "B" WALL
3	ELEVATION "A" & "C" WALL
4	FLOOR PLAN
5	ROOF PLAN
6	SYSTEM DETAILS
7	SYSTEM DETAILS
8	SYSTEM DETAILS

DATE	7/9/24
DRAWN	MTS
SCALE	NTS
SHEET	1 OF 8

ELLIE De LIA
7633 NORTH LINKS WAY
FOX POINT, WI 53217
JOB #39712

MILWAUKEE
W141N9296 FOUNTAIN BLVD
MENOMONEE FALLS, WI 53051
262-798-0500




ERIC OETJEN, P.E., M. ENG.
WI. PROFESSIONAL ENGINEER
(WI. LIC. #100913-6)
5 GREENE STREET
FORT THOMAS, KY. 41075
PH. # 859-393-9049



07-14-2024

THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.



ELEVATION - "B" WALL



07-14-2024

DATE	7/9/24	-
DRAWN	MTS	-
SCALE	1/4" = 1'-0"	-
SHEET	2 OF 8	-


ELLIE De LIA
7633 NORTH LINKS WAY
FOX POINT, WI 53217
JOB #39712

MILWAUKEE
W141N9296 FOUNTAIN BLVD
MENOMONEE FALLS, WI 53051
262-798-0500



ERIC OETJEN, P.E., M. ENG.
WI. PROFESSIONAL ENGINEER
(WI. LIC. #100913-6)
5 GREENE STREET
FORT THOMAS, KY. 41075
PH. # 859-393-9049

THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, L.L.C., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.



ELEVATION - "A" WALL

ELEVATION - "C" WALL

DATE	7/9/24
DRAWN	MTS
SCALE	1/4" = 1'-0"
SHEET	3 OF 8

ELLIE De LIA
 7633 NORTH LINKS WAY
 FOX POINT, WI 53217
 JOB #39712


MILWAUKEE
 W141N9296 FOUNTAIN BLVD
 MENOMONEE FALLS, WI 53051
 262-798-0500



ERIC OETJEN, P.E., M. ENG.
 WI. PROFESSIONAL ENGINEER
 (WI. LIC. #100913-6)
 5 GREENE STREET
 FORT THOMAS, KY. 41075
 PH. # 859-393-9049



THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.



FLOOR PLAN

DATE	7/9/24
DRAWN	MTS
SCALE	1/4" = 1'-0"
SHEET	4 OF 8

ELLIE De LIA
7633 NORTH LINKS WAY
FOX POINT, WI 53217
JOB #39712



MILWAUKEE
W141N9296 FOUNTAIN BLVD
MENOMONEE FALLS, WI 53051
262-798-0500



ERIC OETJEN, P.E., M. ENG.
WI. PROFESSIONAL ENGINEER
(WI. LIC. #100913-6)
5 GREENE STREET
FORT THOMAS, KY. 41075
PH. # 859-393-9049



THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.



DATE	7/9/24
DRAWN	MTS
SCALE	1/4" = 1'-0"
SHEET	5 OF 8


ELLIE De LIA
7633 NORTH LINKS WAY
FOX POINT, WI 53217
JOB #39712

MILWAUKEE
W141N9296 FOUNTAIN BLVD
MENOMONEE FALLS, WI 53051
262-798-0500




ERIC OETJEN, P.E., M. ENG.
WI. PROFESSIONAL ENGINEER
(WI. LIC. #100913-6)
5 GREENE STREET
FORT THOMAS, KY. 41075
PH. # 859-393-9049


THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC. AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.




PLAN VIEW OF SUPER FOAM FILL PANEL CONNECTION @ EXISTING WALL




PLAN VIEW OF MASTER FRAME JAMB, SUPER FOAM FILL PANEL, & E.R. WALL POST CONNECTION @ 4x4 WOOD POST



PLAN VIEW OF MASTER FRAME JAMBS CONNECTION @ GANGING POST



PLAN VIEW OF MASTER FRAME JAMBS & E.R. WALL POST CONNECTION @ CORNER POST



PLAN VIEW OF MASTER FRAME JAMBS CONNECTION @ 4x6 WOOD POST

ANCHORING NOTES:
 3/8" DIA. ANCHOR BOLTS
 3 1/2" LONG GALV. LAG
 SCREWS INTO WOOD; 3"
 LONG DEWALT SCREW-
 BOLT+ INTO CONCRETE,
 SET CENTER OF ANCHORS
 AT LEAST 2" FROM EDGE OF
 SUPPORTING MATERIAL

DATE	7/9/24
DRAWN	MTS
SCALE	1 1/2" = 1'-0"
SHEET	6 OF 8

ELLIE De LIA
 7633 NORTH LINKS WAY
 FOX POINT, WI 53217
 JOB #39712


MILWAUKEE
 W141N9296 FOUNTAIN BLVD
 MENOMONEE FALLS, WI 53051
 262-798-0500




ERIC OETJEN, P.E., M. ENG.
 WI. PROFESSIONAL ENGINEER
 (WI. LIC. #100913-6)
 5 GREENE STREET
 FORT THOMAS, KY. 41075
 PH. # 859-393-9049




THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, L.L.C., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.




SECTION THROUGH FOAM KNEEWALL
CONNECTION @ DECK FOUNDATION




SECTION THROUGH MASTER FRAME SILL
CONNECTION @ DECK FOUNDATION




FRONT VIEW THROUGH 4x6 RIDGE POST
CONNECTION @ DECK FOUNDATION



SECTION THROUGH MASTER FRAME SILL
CONNECTION @ FOAM KNEEWALL



SECTION THROUGH MASTER FRAME HEAD
CONNECTION @ GLASS TRANSOM



SECTION THROUGH "H" & MASTER FRAME
HEAD CONNECTION @ GLASS WING

DATE	7/9/24
DRAWN	MTS
SCALE	1 1/2" = 1'-0"
SHEET	7 OF 8

ELLIE De LIA
7633 NORTH LINKS WAY
FOX POINT, WI 53217
JOB #39712


MILWAUKEE
W141N9296 FOUNTAIN BLVD
MENOMONEE FALLS, WI 53051
262-798-0500




ERIC OETJEN, P.E., M. ENG.
WI. PROFESSIONAL ENGINEER
(WI. LIC. #100913-6)
5 GREENE STREET
FORT THOMAS, KY. 41075
PH. # 859-393-9049




THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.




SECTION THROUGH 6" SUPER FOAM ROOF
PANEL CONNECTION @ GLASS WING




SECTION THROUGH MASTER FRAME & HEADER
CONNECTION @ 6" SUPER FOAM ROOF




SECTION THROUGH TRANSOM & HEADER
CONNECTION @ 6" SUPER FOAM ROOF



SECTION THROUGH 6" SUPER FOAM ROOF & PANEL
HANGER ASSEMBLY CONNECTION @ RIDGE BEAM



6" ROOF PANEL & I BEAM
CONNECTION @ EXISTING WALL



SECTION THROUGH 6" ROOF
CONNECTION @ I BEAM

DATE	7/9/24
DRAWN	MTS
SCALE	1 1/2" = 1'-0"
SHEET	8 OF 8

ELLIE De LIA
7633 NORTH LINKS WAY
FOX POINT, WI 53217
JOB #39712

MILWAUKEE
W141N9296 FOUNTAIN BLVD
MENOMONEE FALLS, WI 53051
262-798-0500



ERIC OETJEN, P.E., M. ENG.
WI. PROFESSIONAL ENGINEER
(WI. LIC. #100913-6)
5 GREENE STREET
FORT THOMAS, KY. 41075
PH. # 859-393-9049



THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.

MINIMUM DESIGN LOADS: PER WISCONSIN SPS 320-325 / 2018 UDC / ASCE 7-05

NOTE: COMPONENTS HAVE BEEN CHECKED AGAINST DESIGN LOADS SHOWN & FOUND TO BE ACCEPTABLE STRUCTURALLY

DEAD LOADS:
1. ROOF: 6 PSF
2. WALLS: 6 PSF

SNOW LOADS: GROUND SNOW LOAD 30 PSF

WIND PRESSURE: 20 PSF

LIVE LOADS: ROOF: 30 PSF

DEFLECTION LIMITS:
1. ROOF: L/120
2. WALLS: L/175

THIS THERMALLY ISOLATED SUNROOM IS UNCONDITIONED AND NOT HABITABLE

NOTE: THE P.E. STAMP ON THESE DRAWINGS ADDRESS ONLY THE GDI MANUFACTURED COMPONENTS, & THE ANCHORAGE OF THESE COMPONENTS TO THE EXISTING STRUCTURE.

NOTES:

1. ALLVIEW (CA5) SUNROOM; WHITE IN COLOR
2. CONSTRUCT SUNROOM ON EXISTING DECK
3. ELECTRICAL BY GDI
4. CONCRETE
 - A) CONCRETE WORK SHALL CONFORM TO ALL REQUIREMENTS OF ACI 301 SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS.
 - B) ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI AT 28 DAYS. EXTERIOR FLOORS AND EXPOSED CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4500 PSI AND 5% TO 7% AIR ENTRAINMENT.
5. WOOD
 - A) MATERIALS - FRAMING LUMBER
 - i) WOOD POSTS: NO. 2 GRADE (OR BETTER) SOUTHERN PINE OR DOUGLAS FIR
 - ii) 2x8, 2x10, 2x12 NO. 2 GRADE (OR BETTER) SOUTHERN PINE OR DOUGLAS FIR
 - B) WOOD MEMBERS SHALL BE PRESSURE-TREATED FOR THE FOLLOWING CONDITIONS:
 - i) IN DIRECT CONTACT WITH THE GROUND
 - ii) SILLS OR PLATES ON CONCRETE WITHIN 8" OF FINISHED GRADE
 - iii) JOISTS AND SUBFLOORS WITHIN 18" OF FINISH GRADE AND BEAMS WITHIN 12" OF FINISH GRADE
 - iv) EXPOSED EXTERIOR DECKS
 - C) FASTENERS
ALL FASTENERS AND HARDWARE USED TO CONNECT TO PRESSURE TREATED WOOD MEMBERS SHALL EITHER BE 304 OR 316 STAINLESS STEEL, OR HOT DIPPED GALVANIZED PER ASTM-A653 COATING DESIGNATION G-185 AND ASTM-A153
6. STRUCTURAL ALUMINUM
 - A) ALL EXTRUSIONS SHALL BE COMMERCIAL GRADE ALUMINUM SUPPLIED BY GREAT DAY IMPROVEMENTS, LLC.
 - B) ROOF PANELS SHALL BE 3" OR 6" THICK SUPER FOAM ROOF PANELS FACED WITH A 0.024" ALUMINUM SKIN TOP AND BOTTOM.
7. THIS SUNROOM IS CONSIDERED AS NON-CONDITIONED SPACE, EXEMPT FROM ENERGY REQUIREMENTS

GREAT DAY IMPROVEMENTS
PATIO ENCLOSURES, MILWAUKEE
De LIA RESIDENCE

SHEET #	DESCRIPTION
1	COVER
2	ELEVATION "B" WALL
3	ELEVATION "A" & "C" WALL
4	FLOOR PLAN
5	ROOF PLAN
6	SYSTEM DETAILS
7	SYSTEM DETAILS
8	SYSTEM DETAILS

DATE	7/9/24
DRAWN	MTS
SCALE	NTS
SHEET	1 OF 8

ELLIE De LIA
7633 NORTH LINKS WAY
FOX POINT, WI 53217
JOB #39712

MILWAUKEE
W141N9296 FOUNTAIN BLVD
MENOMONEE FALLS, WI 53051
262-798-0500




ERIC OETJEN, P.E., M. ENG.
WI. PROFESSIONAL ENGINEER
(WI. LIC. #100913-6)
5 GREENE STREET
FORT THOMAS, KY. 41075
PH. # 859-393-9049



THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.

THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.



ELEVATION - "B" WALL

DATE	7/9/24
DRAWN	MTS
SCALE	1/4" = 1'-0"
SHEET	2 OF 8

ELLIE De LIA
 7633 NORTH LINKS WAY
 FOX POINT, WI 53217
 JOB #39712


MILWAUKEE
 W141N9296 FOUNTAIN BLVD
 MENOMONEE FALLS, WI 53051
 262-798-0500




ERIC OETJEN, P.E., M. ENG.
 WI. PROFESSIONAL ENGINEER
 (WI. LIC. #100913-6)
 5 GREENE STREET
 FORT THOMAS, KY. 41075
 PH. # 859-393-9049



THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.



ELEVATION - "A" WALL



ELEVATION - "C" WALL

DATE	7/9/24	-
DRAWN	MTS	-
SCALE	1/4" = 1'-0"	-
SHEET	3 OF 8	-


ELLIE De LIA
 7633 NORTH LINKS WAY
 FOX POINT, WI 53217
 JOB #39712

MILWAUKEE
 W141N9296 FOUNTAIN BLVD
 MENOMONEE FALLS, WI 53051
 262-798-0500



ERIC OETJEN, P.E., M. ENG.
 WI. PROFESSIONAL ENGINEER
 (WI. LIC. #100913-6)
 5 GREENE STREET
 FORT THOMAS, KY. 41075
 PH. # 859-393-9049





FLOOR PLAN

DATE	7/9/24	-
DRAWN	MTS	-
SCALE	1/4" = 1'-0"	-
SHEET	4 OF 8	-

ELLIE De LIA
 7633 NORTH LINKS WAY
 FOX POINT, WI 53217
 JOB #39712



MILWAUKEE
 W141N9296 FOUNTAIN BLVD
 MENOMONEE FALLS, WI 53051
 262-798-0500



ERIC OETJEN, P.E., M. ENG.
 WI. PROFESSIONAL ENGINEER
 (WI. LIC. #100913-6)
 5 GREENE STREET
 FORT THOMAS, KY. 41075
 PH. # 859-393-9049



THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.



DATE	7/9/24
DRAWN	MTS
SCALE	1/4" = 1'-0"
SHEET	5 OF 8

ELLIE De LIA
7633 NORTH LINKS WAY
FOX POINT, WI 53217
JOB #39712


MILWAUKEE
W141N9296 FOUNTAIN BLVD
MENOMONEE FALLS, WI 53051
262-798-0500




ERIC OETJEN, P.E., M. ENG.
WI. PROFESSIONAL ENGINEER
(WI. LIC. #100913-6)
5 GREENE STREET
FORT THOMAS, KY. 41075
PH. # 859-393-9049




THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC. AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.




PLAN VIEW OF SUPER FOAM FILL PANEL CONNECTION @ EXISTING WALL




PLAN VIEW OF MASTER FRAME JAMB, SUPER FOAM FILL PANEL, & E.R. WALL POST CONNECTION @ 4x4 WOOD POST



PLAN VIEW OF MASTER FRAME JAMBS CONNECTION @ GANGING POST



PLAN VIEW OF MASTER FRAME JAMBS & E.R. WALL POST CONNECTION @ CORNER POST



PLAN VIEW OF MASTER FRAME JAMBS CONNECTION @ 4x6 WOOD POST



07-14-2024

DATE	7/9/24
DRAWN	MTS
SCALE	1 1/2" = 1'-0"
SHEET	6 OF 8


ELLIE De LIA
7633 NORTH LINKS WAY
FOX POINT, WI 53217
JOB #39712

MILWAUKEE
W141N9296 FOUNTAIN BLVD
MENOMONEE FALLS, WI 53051
262-798-0500




ERIC OETJEN, P.E., M. ENG.
WI. PROFESSIONAL ENGINEER
(WI. LIC. #100913-6)
5 GREENE STREET
FORT THOMAS, KY. 41075
PH. # 859-393-9049


THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.




SECTION THROUGH FOAM KNEEWALL
CONNECTION @ DECK FOUNDATION




SECTION THROUGH MASTER FRAME SILL
CONNECTION @ DECK FOUNDATION




FRONT VIEW THROUGH 4x6 RIDGE POST
CONNECTION @ DECK FOUNDATION



SECTION THROUGH MASTER FRAME SILL
CONNECTION @ FOAM KNEEWALL



SECTION THROUGH MASTER FRAME HEAD
CONNECTION @ GLASS TRANSOM



SECTION THROUGH "H" & MASTER FRAME
HEAD CONNECTION @ GLASS WING

DATE	7/9/24	-
DRAWN	MTS	-
SCALE	1 1/2" = 1'-0"	-
SHEET	7 OF 8	-

ELLIE De LIA
7633 NORTH LINKS WAY
FOX POINT, WI 53217
JOB #39712


MILWAUKEE
W141N9296 FOUNTAIN BLVD
MENOMONEE FALLS, WI 53051
262-798-0500




ERIC OETJEN, P.E., M. ENG.
WI. PROFESSIONAL ENGINEER
(WI. LIC. #100913-6)
5 GREENE STREET
FORT THOMAS, KY. 41075
PH. # 859-393-9049




THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.




SECTION THROUGH 6" SUPER FOAM ROOF
PANEL CONNECTION @ GLASS WING




SECTION THROUGH MASTER FRAME & HEADER
CONNECTION @ 6" SUPER FOAM ROOF




SECTION THROUGH TRANSOM & HEADER
CONNECTION @ 6" SUPER FOAM ROOF



SECTION THROUGH 6" SUPER FOAM ROOF & PANEL
HANGER ASSEMBLY CONNECTION @ RIDGE BEAM



6" ROOF PANEL & I BEAM
CONNECTION @ EXISTING WALL



SECTION THROUGH 6" ROOF
CONNECTION @ I BEAM

DATE	7/9/24
DRAWN	MTS
SCALE	1 1/2" = 1'-0"
SHEET	8 OF 8

ELLIE De LIA
7633 NORTH LINKS WAY
FOX POINT, WI 53217
JOB #39712

MILWAUKEE
W141N9296 FOUNTAIN BLVD
MENOMONEE FALLS, WI 53051
262-798-0500



ERIC OETJEN, P.E., M. ENG.
WI. PROFESSIONAL ENGINEER
(WI. LIC. #100913-6)
5 GREENE STREET
FORT THOMAS, KY. 41075
PH. # 859-393-9049



07-14-2024

THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.

MINIMUM DESIGN LOADS: PER WISCONSIN SPS 320-325 / 2018 UDC / ASCE 7-05

NOTE: COMPONENTS HAVE BEEN CHECKED AGAINST DESIGN LOADS SHOWN & FOUND TO BE ACCEPTABLE STRUCTURALLY

DEAD LOADS:
1. ROOF: 6 PSF
2. WALLS: 6 PSF

SNOW LOADS: GROUND SNOW LOAD 30 PSF

WIND PRESSURE: 20 PSF

LIVE LOADS: ROOF: 30 PSF

DEFLECTION LIMITS:
1. ROOF: L/120
2. WALLS: L/175

THIS THERMALLY ISOLATED SUNROOM IS UNCONDITIONED AND NOT HABITABLE

NOTE: THE P.E. STAMP ON THESE DRAWINGS ADDRESS ONLY THE GDI MANUFACTURED COMPONENTS, & THE ANCHORAGE OF THESE COMPONENTS TO THE EXISTING STRUCTURE.

NOTES:

1. ALLVIEW (CA5) SUNROOM; WHITE IN COLOR
2. CONSTRUCT SUNROOM ON EXISTING DECK
3. ELECTRICAL BY GDI
4. CONCRETE
 - A) CONCRETE WORK SHALL CONFORM TO ALL REQUIREMENTS OF ACI 301 SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS.
 - B) ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI AT 28 DAYS. EXTERIOR FLOORS AND EXPOSED CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4500 PSI AND 5% TO 7% AIR ENTRAINMENT.
5. WOOD
 - A) MATERIALS - FRAMING LUMBER
 - i) WOOD POSTS: NO. 2 GRADE (OR BETTER) SOUTHERN PINE OR DOUGLAS FIR
 - ii) 2x8, 2x10, 2x12 NO. 2 GRADE (OR BETTER) SOUTHERN PINE OR DOUGLAS FIR
 - B) WOOD MEMBERS SHALL BE PRESSURE-TREATED FOR THE FOLLOWING CONDITIONS:
 - i) IN DIRECT CONTACT WITH THE GROUND
 - ii) SILLS OR PLATES ON CONCRETE WITHIN 8" OF FINISHED GRADE
 - iii) JOISTS AND SUBFLOORS WITHIN 18" OF FINISH GRADE AND BEAMS WITHIN 12" OF FINISH GRADE
 - iv) EXPOSED EXTERIOR DECKS
 - C) FASTENERS

ALL FASTENERS AND HARDWARE USED TO CONNECT TO PRESSURE TREATED WOOD MEMBERS SHALL EITHER BE 304 OR 316 STAINLESS STEEL, OR HOT DIPPED GALVANIZED PER ASTM-A653 COATING DESIGNATION G-185 AND ASTM-A153
6. STRUCTURAL ALUMINUM
 - A) ALL EXTRUSIONS SHALL BE COMMERCIAL GRADE ALUMINUM SUPPLIED BY GREAT DAY IMPROVEMENTS, LLC.
 - B) ROOF PANELS SHALL BE 3" OR 6" THICK SUPER FOAM ROOF PANELS FACED WITH A 0.024" ALUMINUM SKIN TOP AND BOTTOM.
7. THIS SUNROOM IS CONSIDERED AS NON-CONDITIONED SPACE, EXEMPT FROM ENERGY REQUIREMENTS

GREAT DAY IMPROVEMENTS
PATIO ENCLOSURES, MILWAUKEE
De LIA RESIDENCE

SHEET #	DESCRIPTION
1	COVER
2	ELEVATION "B" WALL
3	ELEVATION "A" & "C" WALL
4	FLOOR PLAN
5	ROOF PLAN
6	SYSTEM DETAILS
7	SYSTEM DETAILS
8	SYSTEM DETAILS

DATE	7/9/24
DRAWN	MTS
SCALE	NTS
SHEET	1 OF 8

ELLIE De LIA
7633 NORTH LINKS WAY
FOX POINT, WI 53217
JOB #39712


MILWAUKEE
W141N9296 FOUNTAIN BLVD
MENOMONEE FALLS, WI 53051
262-798-0500



ERIC OETJEN, P.E., M. ENG.
WI. PROFESSIONAL ENGINEER
(WI. LIC. #100913-6)
5 GREENE STREET
FORT THOMAS, KY. 41075
PH. # 859-393-9049



THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.



ELEVATION - "B" WALL



DATE	7/9/24
DRAWN	MTS
SCALE	1/4" = 1'-0"
SHEET	2 OF 8

ELLIE De LIA
 7633 NORTH LINKS WAY
 FOX POINT, WI 53217
 JOB #39712


MILWAUKEE
 W141N9296 FOUNTAIN BLVD
 MENOMONEE FALLS, WI 53051
 262-798-0500




ERIC OETJEN, P.E., M. ENG.
 WI. PROFESSIONAL ENGINEER
 (WI. LIC. #100913-6)
 5 GREENE STREET
 FORT THOMAS, KY. 41075
 PH. # 859-393-9049

07-14-2024

THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, L.L.C., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.



ELEVATION - "A" WALL



ELEVATION - "C" WALL

DATE	7/9/24
DRAWN	MTS
SCALE	1/4" = 1'-0"
SHEET	3 OF 8

ELLIE De LIA
 7633 NORTH LINKS WAY
 FOX POINT, WI 53217
 JOB #39712


MILWAUKEE
 W141N9296 FOUNTAIN BLVD
 MENOMONEE FALLS, WI 53051
 262-798-0500



ERIC OETJEN, P.E., M. ENG.
 WI. PROFESSIONAL ENGINEER
 (WI. LIC. #100913-6)
 5 GREENE STREET
 FORT THOMAS, KY. 41075
 PH. # 859-393-9049



THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.



FLOOR PLAN

DATE	7/9/24	-
DRAWN	MTS	-
SCALE	1/4" = 1'-0"	-
SHEET	4 OF 8	-

ELLIE De LIA
 7633 NORTH LINKS WAY
 FOX POINT, WI 53217
 JOB #39712



MILWAUKEE
 W141N9296 FOUNTAIN BLVD
 MENOMONEE FALLS, WI 53051
 262-798-0500



ERIC OETJEN, P.E., M. ENG.
 WI. PROFESSIONAL ENGINEER
 (WI. LIC. #100913-6)
 5 GREENE STREET
 FORT THOMAS, KY. 41075
 PH. # 859-393-9049



THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.



DATE	7/9/24
DRAWN	MTS
SCALE	1/4" = 1'-0"
SHEET	5 OF 8

ELLIE De LIA
7633 NORTH LINKS WAY
FOX POINT, WI 53217
JOB #39712


MILWAUKEE
W141N9296 FOUNTAIN BLVD
MENOMONEE FALLS, WI 53051
262-798-0500




ERIC OETJEN, P.E., M. ENG.
WI. PROFESSIONAL ENGINEER
(WI. LIC. #100913-6)
5 GREENE STREET
FORT THOMAS, KY. 41075
PH. # 859-393-9049

07-14-2024


THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.




PLAN VIEW OF SUPER FOAM FILL PANEL CONNECTION @ EXISTING WALL




PLAN VIEW OF MASTER FRAME JAMB, SUPER FOAM FILL PANEL, & E.R. WALL POST CONNECTION @ 4x4 WOOD POST




PLAN VIEW OF MASTER FRAME JAMBS CONNECTION @ GANGING POST



PLAN VIEW OF MASTER FRAME JAMBS & E.R. WALL POST CONNECTION @ CORNER POST



PLAN VIEW OF MASTER FRAME JAMBS CONNECTION @ 4x6 WOOD POST



07-14-2024

DATE	7/9/24
DRAWN	MTS
SCALE	1 1/2" = 1'-0"
SHEET	6 OF 8


ELLIE De LIA
7633 NORTH LINKS WAY
FOX POINT, WI 53217
JOB #39712

MILWAUKEE
W141N9296 FOUNTAIN BLVD
MENOMONEE FALLS, WI 53051
262-798-0500




ERIC OETJEN, P.E., M. ENG.
WI. PROFESSIONAL ENGINEER
(WI. LIC. #100913-6)
5 GREENE STREET
FORT THOMAS, KY. 41075
PH. # 859-393-9049


THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.




SECTION THROUGH FOAM KNEEWALL
CONNECTION @ DECK FOUNDATION




SECTION THROUGH MASTER FRAME SILL
CONNECTION @ DECK FOUNDATION




FRONT VIEW THROUGH 4x6 RIDGE POST
CONNECTION @ DECK FOUNDATION



SECTION THROUGH MASTER FRAME SILL
CONNECTION @ FOAM KNEEWALL



SECTION THROUGH MASTER FRAME HEAD
CONNECTION @ GLASS TRANSOM



SECTION THROUGH "H" & MASTER FRAME
HEAD CONNECTION @ GLASS WING

DATE	7/9/24
DRAWN	MTS
SCALE	1 1/2" = 1'-0"
SHEET	7 OF 8

ELLIE De LIA
7633 NORTH LINKS WAY
FOX POINT, WI 53217
JOB #39712


MILWAUKEE
W141N9296 FOUNTAIN BLVD
MENOMONEE FALLS, WI 53051
262-798-0500




ERIC OETJEN, P.E., M. ENG.
WI. PROFESSIONAL ENGINEER
(WI. LIC. #100913-6)
5 GREENE STREET
FORT THOMAS, KY. 41075
PH. # 859-393-9049




THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, LLC... AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.




SECTION THROUGH 6" SUPER FOAM ROOF
PANEL CONNECTION @ GLASS WING




SECTION THROUGH MASTER FRAME & HEADER
CONNECTION @ 6" SUPER FOAM ROOF




SECTION THROUGH TRANSOM & HEADER
CONNECTION @ 6" SUPER FOAM ROOF



SECTION THROUGH 6" SUPER FOAM ROOF & PANEL
HANGER ASSEMBLY CONNECTION @ RIDGE BEAM



6" ROOF PANEL & I BEAM
CONNECTION @ EXISTING WALL



SECTION THROUGH 6" ROOF
CONNECTION @ I BEAM

DATE	7/9/24
DRAWN	MTS
SCALE	1 1/2" = 1'-0"
SHEET	8 OF 8

ELLIE De LIA
7633 NORTH LINKS WAY
FOX POINT, WI 53217
JOB #39712


MILWAUKEE
W141N9296 FOUNTAIN BLVD
MENOMONEE FALLS, WI 53051
262-798-0500



ERIC OETJEN, P.E., M. ENG.
WI. PROFESSIONAL ENGINEER
(WI. LIC. #100913-6)
5 GREENE STREET
FORT THOMAS, KY. 41075
PH. # 859-393-9049



THIS DRAWING IS PROPERTY OF GREAT DAY IMPROVEMENTS, L.L.C., AND DUPLICATION OF THIS DRAWING WITHOUT OUR EXPRESSED WRITTEN CONSENT IS PROHIBITED. ALL RIGHTS RESERVED.



VILLAGE OF FOX POINT

7200 N Santa Monica Blvd
Fox Point, WI 53217
(414) 247-6622
www.villageoffoxpoint.com

Permit Number:

B-

OFFICE USE ONLY
Issued Date
Zoning B-SS

BUILDING PERMIT

Job Address 7528 N Links Way
Building Type: Residential [checked] Commercial
Description of Work
200 SF Addition to Garage for additional Storage
Estimated Cost of Project \$ 2,000

Owner/Occupant Brian G Wolff
Business Name
Address 7528 N Links Way
Phone 414-839-3040
Contact Name
City/State/Zip Fox Point/WI/53217
Email briarch@icloud.com

Cautionary Statement required when homeowner is applying for permit

Contractor
Company Name Self
Address
Phone
Dwelling Contractor #
Contact Name
City/State/Zip
Email
Dwelling Contractor Qualifier #

Square Footage Under Construction
1st Floor 2nd Floor Basement Addition 200 Garage

Table with 3 columns: Description, Rate, Amount. Includes items like Project - Per \$1,000 of estimated cost, Building Board, Footing early start, etc. Total Permit Fee \$145.00

Applicant Signature [Signature] Date 8/24/2024

ISSUED PERMITS are available on the Village website under PERMITS & LICENSES

Receipt No: 22.000013 Aug 28, 2024

7528 N LINKS WAY

Previous Balance: .00
LICENSES & PERMITS
BUILDING PLANS - FILING 75.00
FEE

Total: 75.00
=====

LICENSES & PERMITS
BUILDING PERMIT 70.00

Total: 70.00
=====

ONLINE - CREDIT CARD 145.00

Payor:
ERIK BOWIE

Total Applied: 145.00

Change Tendered: .00
=====


08/28/2024 10:00 AM

VILLAGE OF FOX POINT
7200 N. SANTA MONICA BLVD
FOX POINT WI 53217 414-351-8900

COMPLETE AND ACCURATE
SURVEYS ANYWHERE


HAROLD W. WARD
ENGINEER AND SURVEYOR
MILWAUKEE - WISCONSIN

SUCCESSOR TO
W. B. ENGELHARDT



PROPERTY AT 1545 LINKS WAY HARVEY E. ABITZ - OWNER
LEGAL DESCRIPTION: LOT 8 BLOCK 1 LAKE DRIVE MANOR, IN THE
S 1/4 OF SEC. 16, T. 9 N. E. 22 E. VILLAGE OF FOX POINT WIS
SCALE 1"=20'

E CALUMET RD.



State of Wisconsin,
County of Milwaukee

I hereby certify that I have made the above survey on the nineteenth day
of July 1947 and that the information relative to all buildings shown
on said survey, is complete and correct.

Plot No. 46-1545 S


Signed Harold W. Ward
Engineer and Surveyor

APPENDIX A

A.1 Existing Photos




View Facing West t Elevation of Garage



Corner of Garage Slab - Approx. 10"



Corner of Garage Slab - Approx. 10"



Interior View of Rafters



APPENDIX B

B.1 Code References

B.2 Woodworks Design

Check Calc. Sheet

B.3 Fastener Schedule

Chapter SPS 321 CONSTRUCTION STANDARDS

Subchapter I — Scope

SPS 321.01 Scope.

Subchapter II — Design Criteria

- SPS 321.02 Loads and materials.
- SPS 321.03 Exits.
- SPS 321.035 Interior circulation.
- SPS 321.04 Stairways and elevated areas.
- SPS 321.042 Ladders.
- SPS 321.045 Ramps.
- SPS 321.05 Natural light and natural ventilation.
- SPS 321.06 Ceiling height.
- SPS 321.07 Attic and crawl space access.
- SPS 321.08 Fire separation and dwelling unit separation.
- SPS 321.085 Fireblocking.
- SPS 321.09 Smoke detectors.
- SPS 321.095 Automatic fire sprinklers.
- SPS 321.097 Carbon monoxide alarms.
- SPS 321.10 Protection against decay and termites.
- SPS 321.11 Foam plastic.
- SPS 321.115 Installation of elevators or dumbwaiters.

Subchapter III — Excavations

- SPS 321.12 Drainage.
- SPS 321.125 Erosion control and sediment control.
- SPS 321.13 Excavations adjacent to adjoining property.
- SPS 321.14 Excavations for footings and foundations.

Subchapter IV — Footings

- SPS 321.15 Footings.
- SPS 321.16 Frost protection.
- SPS 321.17 Drain tiles.

Subchapter V — Foundations

SPS 321.18 Foundations.

Subchapter VI — Floors

- SPS 321.19 Floor design.
- SPS 321.20 Concrete floors.
- SPS 321.203 Garage floors.
- SPS 321.205 Wood floors in contact with the ground.
- SPS 321.21 Precast concrete floors.
- SPS 321.22 Wood frame floors.
- SPS 321.225 Decks.

Subchapter VII — Walls

- SPS 321.23 Wall design.
- SPS 321.24 Exterior covering.
- SPS 321.25 Wood frame walls.
- SPS 321.26 Masonry walls.

Subchapter VIII — Roof and Ceilings

- SPS 321.27 Roof design and framing.
- SPS 321.28 Weather protection for roofs.

Subchapter IX — Fireplace Requirements

- SPS 321.29 Masonry fireplaces.
- SPS 321.30 Masonry chimneys.
- SPS 321.32 Factory-built fireplaces.

Subchapter X — Construction in Floodplains

- SPS 321.33 Construction in floodplains.
- SPS 321.34 Construction in coastal floodplains.

Subchapter XI — Installation of Manufactured Homes

SPS 321.40 Installation standards.

Note: Chapter Ind 21 was renumbered to be chapter ILHR 21, Register, February, 1985, No. 350, eff. 3-1-85. Chapter ILHR 21 was renumbered chapter Comm 21 under s. 13.93 (2m) (b) 1., Stats., and corrections made under s. 13.93 (2m) (b) 6. and 7., Stats., Register, January, 1999, No. 517. Chapter Comm 21 was reprinted to correct the Table of Contents, Register October 2009 No. 646. Chapter Comm 21 was renumbered chapter SPS 321 under s. 13.92 (4) (b) 1., Stats., Register December 2011 No. 672.

Subchapter I — Scope

SPS 321.01 Scope. The provisions of this chapter shall apply to the design and construction of all one- and 2-family dwellings.

History: Cr. Register, November, 1979, No. 287, eff. 6-1-80.

Subchapter II — Design Criteria

SPS 321.02 Loads and materials. Every dwelling shall be designed and constructed in accordance with the requirements of this section.

(1) **DESIGN LOAD.** Every dwelling shall be designed and constructed to support the actual dead load, live loads and wind loads acting upon it without exceeding the allowable stresses of the material. The construction of buildings and structures shall result in a system that provides a complete load path capable of transferring all loads from point of origin through the load-resisting elements to the foundation.

(a) **Dead loads.** Every dwelling shall be designed and constructed to support the actual weight of all components and materials. Earth-sheltered dwellings shall be designed and constructed to support the actual weight of all soil loads.

(b) **Live loads.** 1. 'Floors and ceilings.' Floors and ceilings shall be designed and constructed to support the minimum live loads listed in Table 321.02. The design load shall be applied uniformly over the component area.

Table 321.02-1

Component	Live Load (pounds per sq. ft.)
Floors	40
Garage floors	50
Exterior balconies, decks, porches	40
Ceilings (with storage)	20
Ceilings (without storage)	5

2. 'Snow loads.' Roofs shall be designed and constructed to support the minimum snow loads listed on the zone map. The loads shall be assumed to act vertically over the roof area projected upon a horizontal plane.

(c) **Wind loads.** Dwellings shall be designed and constructed to withstand either a horizontal and uplift pressure of 20 pounds per square foot acting over the surface area or the wind loads determined in accordance with ASCE 7-05, *Minimum Design Loads for Buildings and Other Structures*.

Note: ASCE 7-05 allows for substantial reduction from 20 psf as applied to the surface area.

(2) **METHODS OF DESIGN.** All dwellings shall be designed by the method of structural analysis or the method of accepted practice specified in each part of this code.

Note: See ch. NR 116, rules of the department of natural resources, for special requirements relating to buildings located in flood plain zones. Information regarding the elevation of the regional flood may be obtained from the local zoning official.

(3) **STRUCTURAL STANDARDS.** (a) *General.* Design, construction, installation, practice and structural analysis shall conform to

the following nationally recognized standards.

(b) *Wood.* 1. Except as provided in subd. 1. a. and b., structural lumber, glue-laminated timber, timber pilings and fastenings shall be designed in accordance with the "National Design Specification for Wood Construction" and the "Design Values for Wood Construction," a supplement to the National Design Specification for Wood Construction.

Figure 321.02
ZONE MAP FOR ROOF LOADS




Table 321.25-G
BRACING METHODS^{a, f}

Material	Minimum Brace Material Thickness or Size	Maximum Nominal Wall Height ^b	Minimum Braced Wall Panel Width or Brace Angle	Connection Criteria	
				Minimum Fasteners	Maximum Spacing
Intermittent Bracing Methods					
LIB ^c Let-in bracing	1x4 wood brace (or approved metal brace installed per manufacturer instructions)	10'	45° angle and maximum 16" o.c. stud spacing ^b	2-8d common nails or 3-8d box nails (2 3/8" long x 0.113" diameter)	Per stud and top and bottom plates ^e
DWB Diagonal wood boards	3/4" (1" nominal) for maximum 24" o.c. stud spacing	10'	48"	2-8d box nails (2 3/8" long x 0.113" diameter) or 2 - 1 3/4" long 16-gage staples	Per stud and top and bottom plates ^e
WSP Wood structural panel	3/8" for maximum 16" o.c. stud spacing; 7/16" for maximum 24" o.c. stud spacing	10'	48"	6d common nail or 8d box nail (2 3/8" long x 0.113" diameter); or 7/16"- or 1/2"-crown 16-gage staples, 1 1/4" long	6" edges, 12" field (nails) 3" edges, 6" field (staples)
SFB Structural fiber-board sheathing	1/2" for maximum 16" o.c. stud spacing	10'	48"	1 1/2" long x 0.120" diameter galvanized roofing nails or 1"-crown 16-gage staples, 1 1/4" long	3" edges, 6" field
GB Gypsum board (installed on both sides of wall)	1/2" for maximum 24" o.c. stud spacing	10'	96"	5d cooler nails, or #6 screws	7" edges, 7" field (including top and bottom plates)
Continuous Sheathed Bracing Methods					
CS-WSP ^d Continuous sheathed WSP	3/8" for maximum 16" o.c. stud spacing; 7/16" for maximum 24" o.c. stud spacing	12'	Refer to Table 321.25-H	Same as WSP	Same as WSP
CS-SFB ^d Continuous sheathed SFB	1/2" for maximum 16" o.c. stud spacing			Same as SFB	Same as SFB
Narrow Panel Bracing					
PF Portal frame	7/16"	12'	Refer to Figure 321.25-A	Refer to Figure 321.25-A	Refer to Figure 321.25-A

^aThe interior side of all exterior walls shall be sheathed with minimum 1/2-inch gypsum wallboard unless otherwise permitted to be excluded by this subsection. All edges of panel-type wall bracing, except horizontal joints in GB bracing, shall be attached to framing or blocking.

^bThe actual measured wall height shall include stud height and thickness of top and bottom plates. The actual wall height shall be permitted to exceed the listed nominal values by not more than 4 1/2 inches. Tabulated bracing amounts in s. SPS 321.25 (8) (c) are based on a 10-foot nominal wall height for all bracing methods and shall be permitted to be adjusted to other nominal wall heights not exceeding 12 feet in accordance with footnotes to Table 321.25-I or Table 321.25-J.

^cLIB is not permitted for walls supporting a roof and two floors. Two LIB braces installed at a 60° angle from horizontal shall be permitted to be substituted for each 45° angle LIB brace.

^dBracing with CS-WSP and CS-SFB shall have sheathing installed on all sheathable surfaces above, below, and between wall openings.

^eShall be attached to the top and bottom plates and any intermediate studs, in one continuous length.

^fEach braced panel may contain no more than one hole, having a maximum dimension of no more than ten percent of the least dimension of the panel, and confined to the middle three-fourths of the panel.


Table 321.25-H^{a, b}
MINIMUM WIDTHS OF CS-WSP AND CS-SFB BRACED WALL PANELS

Maximum Opening Height Adjacent to Braced Wall Panel	Minimum Width of Full-Height Braced Wall Panel (inches)			
	8' Tall Wall	9' Tall Wall	10' Tall Wall	12' Tall Wall
5' - 4"	24	27	30	36
6' - 8"	32	30	30	36
8'	48	41	38	36
9'	-	54	46	41
10'	-	-	60	48
12'	-	-	-	72


^aSheathing shall extend from the top of the top plate to the bottom of the bottom plate and may be multiple sheets. All joints shall be blocked.

^bInterpolation is permitted.


**FIGURE 321.25-B
DEFINING BUILDING SIDES AND LENGTHS WITH ONE OR MORE
CIRCUMSCRIBED RECTANGLES^{a,b,c}**



(1) Basic floor plan



(2) Angled-building-side plan^d



(3) Angled floor plan^e

^aEach floor plan level shall be circumscribed with one or more rectangles around the entire floor plan at the floor level under consideration as shown. When multiple rectangles are used, each side shall be braced as though it were a separate building and the bracing amount added together along the common wall where adjacent rectangles overlap or abut.


^bRectangles shall surround all enclosed plan offsets and projections. Chimneys, partial height projections, and open structures, such as carports and decks, shall be excluded from the rectangle.

^cEach rectangle shall have a maximum rectangle length-to-width ratio of 3:1.

^dProjected contributing lengths of angled braced wall panels shall be assigned to the closest rectangle sides, as shown for the angled corner in the angled-building-side-plan shown above.

^eBraced wall panels located on a common wall where angled rectangles intersect, as shown in Figure 321.25-B(3), shall have their contributing length applied towards the required length of bracing for the parallel rectangle side and its projected contributing lengths towards the adjacent angled rectangle sides. Where the common side of rectangle 2 as shown in Figure 321.25-B(3) has no physical wall, the portion shall be designed in accordance with s. SPS 321.25 (8) (a).

TABLE 321.25-1
REQUIRED NUMBER OF INTERMITTENT BRACED WALL PANELS
ON WALLS PARALLEL TO EACH RECTANGLE SIDE
AT EACH FLOOR LEVEL^{a,b,c,d,e,f, h, j}

Wall Supporting:		Required Number of Brace Panels on a Building Side		
		Length of Perpendicular Side (feet) ^g		
		≤25	≤50	≤75
Roof and ceiling only		1 ⁱ	2	3
One floor, roof and ceiling		2	4	6
Two floors, roof and ceiling		3	6	9

^aInterpolation is permitted. Extrapolation to buildings larger than addressed in this table is prohibited.

^bThis table applies to wind exposure category B. For wind exposure category C or D, multiply the number of braced wall panels required by 1.3 or 1.6, respectively.

Wind exposure category B is comprised of urban and suburban areas, wooded areas, or other terrain with numerous closely spaced obstructions having the size of single-family dwellings or larger. Exposure B shall be assumed unless the site meets the definition of another type exposure.

Wind exposure category C is comprised of flat, open country and grasslands with scattered obstructions, including surface undulations or other irregularities, having heights generally less than 30 feet extending more than 1,500 feet from the building site in any quadrant. This exposure also applies to any building located within Exposure B type terrain where the building is directly adjacent to open areas of Exposure C type terrain in any quadrant for a distance of more than 600 feet.

Wind exposure category D is comprised of flat, unobstructed areas exposed to wind flowing over open water for a distance of at least 1 mile. This exposure applies only to those buildings and other structures exposed to the wind coming from over the water. Exposure D extends inland from the shoreline a distance of 1,500 feet or 10 times the height of the building or structure, whichever is greater.

^cTabulated values are based on a nominal wall height of 10 feet. For nominal wall heights other than 10 feet and not more than 12 feet, multiply the required number of brace panels by the following factors: 0.9 for 8 feet, 0.95 for 9 feet, 1.15 for 11 feet, or 1.3 for 12 feet.

^dTabulated values are based on a roof with a top-of-wall-to-ridge height of 10 feet. For top-of-wall-to-ridge heights other than 10 feet, multiply the required number of brace panels by the following factors for each floor level support condition:

Roof only – 0.7 for 5 feet, 1.3 for 15 feet, or 1.6 for 20 feet

Roof + 1 Floor – 0.85 for 5 feet, 1.15 for 15 feet, or 1.3 for 20 feet

Roof + 2 Floors – 0.9 for 5 feet or 1.1 for 15 feet.

^eWhere minimum 1/2-inch gypsum wallboard is not included on the interior side of the wall, multiply the number of braced wall panels by 1.7 for LIB bracing or 1.4 for all other bracing methods, except this increase is not required for the portal frame method.

^fAdjustments in footnotes b to e apply cumulatively. Fractions of panels shall be rounded to the nearest one-half braced wall panel.










^gPerpendicular sides to the front and rear sides are the left and right sides. Perpendicular sides to the left and right sides are the front and rear sides. See Figure 321.25-B.

^hThe following braced wall panel conditions shall be permitted to be counted as one-half a braced wall panel toward meeting the required number of panels: (1) one 60 degree LIB; (2) one 48" GB or one 96" GB with gypsum wallboard on one side; (3) one 36" WSP or SFB braced wall panel for wall heights not more than 9 feet; (4) a 48" WSP or SFB braced wall panel where there is no more than one unblocked horizontal joint; or (5) one PF brace panel complying with Figure 321.25-A.

ⁱThis value of less than 2 serves only as the beginning value for calculation purposes. The resulting value shall be 2 or greater, to be consistent with subd. 2.

^jAny floor, habitable or otherwise, that is contained wholly within the roof rafters or roof trusses is exempt from being considered a floor for purposes of determining wall bracing if the top-of-wall-to-ridge height does not exceed 20 feet and if no opening in the roof exceeds 48 inches in height.

Table 321.25-J
REQUIRED LENGTH OF CONTINUOUS BRACING ON WALLS PARALLEL TO EACH RECTANGLE SIDE AT
EACH FLOOR LEVEL^{a,b,c,d,e,g,h,j}

Top-of-Wall-to-Ridge Height (feet)	Wall Supporting:		Total Required Length (feet) of Full-Height Bracing on Any Side of Rectangle							
			Length of Perpendicular Side (feet) ^f							
			10	20	30	40	50	60	70	80
10	Roof and ceiling only		2.0 ⁱ	3.5 ⁱ	5.0	6.0	7.5	9.0	10.5	12.0
	One floor, roof and ceiling		3.5 ⁱ	6.5	9.0	12.0	14.5	17.0	19.8	22.6
	Two floors, roof and ceiling		5.0	9.5	13.5	17.5	21.5	25.5	29.2	33.4
15	Roof and ceiling only		2.5 ⁱ	4.6	6.5	7.8	9.8	11.7	13.7	15.7
	One floor, roof and ceiling		4.0	7.5	10.4	13.8	16.7	19.6	22.9	26.2
	Two floors, roof and ceiling		5.5	10.5	14.9	19.3	23.7	27.5	32.1	36.7
20	Roof and ceiling only		2.9 ⁱ	5.2	7.3	8.8	11.1	13.2	15.4	17.6
	One floor, roof and ceiling		4.5	8.5	11.8	15.6	18.9	22.1	25.8	29.5
	Two floors, roof and ceiling		6.2	11.9	16.8	21.8	27.3	31.1	36.3	41.5

^aInterpolation is permitted. Extrapolation to buildings larger than addressed in this table is prohibited.

^bThis table applies to wind exposure category B. For wind exposure category C or D, multiply the required length of wall bracing by 1.3 or 1.6, respectively. Wind exposure categories are as defined in Table 321.25-I footnote b.

^cTabulated values are based on a nominal wall height of 10 feet. For nominal wall heights other than 10 feet, multiply the required length of bracing by the following factors: 0.90 for 8 feet, 0.95 for 9 feet, 1.05 for 11 feet, or 1.10 for 12 feet.

^dWhere minimum 1/2-inch gypsum wallboard interior finish is not provided, the required bracing amount for the affected rectangle side shall be multiplied by 1.4, except this increase is not required for the portal frame method.

^eAdjustments in footnotes b to d apply cumulatively.

^fPerpendicular sides to the front and rear sides are the left and right sides. Perpendicular sides to the left and right sides are the front and rear sides. See Figure 321.25-B.


^gContinuous sheathing shall be applied to all surfaces of the wall, including areas between brace panels and above and below wall openings.

^hWhen used on a wall line with continuous sheathing, each portal frame panel is counted for its actual length in contributing toward the length of continuous sheathing used on other portions of the same wall line, such as the building side at a given story level.

ⁱAny value of less than 4.0 in this table serves only as the beginning value for calculation purposes. The resulting value shall be 4.0 or greater, to be consistent with Table 321.25-H and subd. 2.

^jAny floor, habitable or otherwise, that is contained wholly within the roof rafters or roof trusses is exempt from being considered a floor for purposes of determining wall bracing if the top-of-wall-to-ridge height does not exceed 20 feet and if no opening in the roof exceeds 48 inches in height.

Figure 321.25-C

LOCATION OF BRACED WALL PANELS ALONG A BUILDING SIDE^a

(d) *Braced wall panel support.* Braced wall panels shall be supported on floor framing or foundations as follows:

1. Where joists are perpendicular to braced wall lines above or below, blocking shall be provided between the joists at braced wall panel locations to permit fastening of wall plates in accordance with the fastener table in the ch. SPS 325 Appendix A.

2. Where joists are parallel to braced wall lines above or below, a rim joist or other parallel framing member shall be provided at the wall to permit fastening of wall plates in accordance with the fastener table in the ch. SPS 325 Appendix A.

3. Braced wall panels shall be permitted to be supported on cantilevered floor joists meeting the cantilever limits of s. SPS 321.22 (6) provided joists are blocked at the nearest bearing wall location, except such blocking is not required for cantilevers not exceeding 24 inches where a full height rim joist is provided.

History: Cr. Register, November, 1979, No. 287, eff. 6-1-80; cr. (1) (d) and am. (3) (b), Register, February, 1985, No. 350, eff. 3-1-85; r. and recr. (3) (b), am. Table 21.25 B and E, Register, January, 1989, No. 397, eff. 2-1-89; am. (3) (a) and (6), Register, March, 1992, No. 435, eff. 4-1-92; r. and recr. (1) (c), am. Table 21.25-D, cr. Table 21.25-F, Register, November, 1995, No. 479, eff. 12-1-95; am. Table 21.25-A, Register, January, 1999, No. 517, eff. 2-1-99; r. (1) (b) and (c), renum. (1) (d) to be (b), r. and recr. (2), (6) and Tables 21.25-E and F, and am. (3) (b) 3., Register, March, 2001, No. 543, eff. 4-1-01; CR 02-077; r. (3) (c) Register May 2003 No. 569, eff. 8-1-03; CR 08-043; am. (1) (title), r. (1) (b), renum. (1) (a) and (6) (a) 4. to be (1) and (6) (a) 5., r. and recr. Table 21.25-A, cr. (6) (a) 4., (7), (8) and (9) Register March 2009 No. 639, eff. 4-1-09; correction in Figure 21.25-E made under s. 13.92 (4) (b) 7., Stats., Register March 2009 No. 639; CR 09-104; am. 21.25 (8) (e) 2., Table 21.25-H, (9) (b) 3., Table 21.25-J, Figure 21.25-G (c), (9) (c) 4. Register December 2010 No. 660, eff. 1-1-11; correction in (1), (2) (b) 3., (3) (a), (6) (c) 2., (d), (8) (c) 1. d., 2. c., (d), (e) 2., 3., (f) 2., (g) 3., (h) 2. b., (9) (b) 1., 2. b., d., 4. b., c., i., (c) 2. (intro.), b., c., d., 3., 4., 5. a., c., d., g., h., i., Table 321.25-H, Figure 321.25-F, -H to -K made under s. 13.92 (4) (b) 7., Stats., Register December 2011 No. 672; EmR1-403; emerg. am. Table 321.25-A, (7) (d), r. and recr. (8) (b), (c), Tables 321.25-G to 321.25-J, Figures 321.25-A to 321.25-C, r. (8) (d) to (f), renum. (8) (g) (title), (intro.), 1. to 3. to (8) (d) (title), (intro.), 1. to 3., r. (8) (g) 4., (h), (9), Tables 321.25-K, 321.25-L, Figures 321.25-D to 321.25-K, eff. 4-1-14; CR 14-015; am. Table 321.25-A, (7) (d), r. and recr. (8) (b), (c), Tables 321.25-G to 321.25-J, Figures 321.25-A to 321.25-C, r. (8) (d) to (f), renum. (8) (g) (title), (intro.), 1. to 3. to (8) (d) (title), (intro.), 1. to 3., r. (8) (g) 4., (h), (9), Tables 321.25-K, 321.25-L, Figures 321.25-D to 321.25-K Register August 2014 No. 704, eff. 9-1-14; CR 15-041; cr. (2m), renum. (3) (intro.), (a), (b) to (3) (am), (bm), (cm), cr. (3) (am) (title), am Table I (title), Table J (title) Register December 2015 No. 720, eff. 1-1-16; CR 15-043; am. (8) (d) 1., 2. Register December 2015 No. 720, eff. 1-1-16.

SPS 321.26 Masonry walls. Masonry walls shall be constructed in accordance with the requirements of this section.

(1) **COLD WEATHER WORK.** When ambient air temperature is below 40°F, the cold weather construction procedures under ACI 530.1 shall be followed.

Note: The requirements for cold weather work are in sections 1.8 and 1.8C of the 2005 edition of the ACI standard.

(2) **MASONRY UNITS.** (a) *Unused concrete units.* Previously unused concrete masonry units shall conform to the ASTM C 90 standard.

(b) *Unused clay or shale units.* Previously unused clay or shale masonry units shall conform to the appropriate ASTM standard: C 62; C 216; or C 652. Units which will be exposed to weathering or frost action shall be Grade SW as specified in these standards.

(c) *Used masonry units.* All previously used masonry units shall be free from physical defects which interfere with the installation or impair the structural properties of the unit.

(3) **TYPES OF MORTAR.** (a) *Mortar specifications.* The type of mortar shall be determined from Table 321.26-A. The mortar shall conform to the requirements of ASTM C-270.

(b) *Surface bond mortars.* Surface bond mortars for masonry walls shall be mixed in accordance with the proportions specified on the bag.

(4) **MORTAR COMPONENTS.** Mortar components shall comply with the following requirements:

(a) *Water.* Water shall be clean and free of deleterious amounts of acids, alkalis, or organic materials.

(b) *Admixtures or mortar colors.* Admixtures or mortar colors shall not be added to the mortar unless the resulting mortar conforms to the mortar specifications. Only mineral oxide may be used as mortar color and shall not exceed 10% by weight of the cement.

(c) *Mixing.* Mortar shall be mixed for at least 3 minutes after all ingredients have been added with the maximum amount of water to produce a workable consistency. Mortars that have stiffened due to water evaporation shall be retempered by adding

B.2 Woodworks Design Calculation Shee



WoodWorks[®]
SOFTWARE FOR WOOD DESIGN

COMPANY

PROJECT

Aug. 13, 2024 12:04


Wolff_Exist Stud.wwc

Design Check Calculation Sheet
WoodWorks Sizer 2023

Loads:

Load	Type	Distribution	Location [ft]		Magnitude		Unit
			Start	End	Start	End	
Load1	Dead	Axial UDL	(Ecc. = 0.00")		225		plf
Load2	Snow	Axial UDL	(Ecc. = 0.00")		450		plf
Load3	Wind	Full Area			8.00 (24.0")		psf
Self-weight	Dead	Axial UDL			4		plf

Reactions (lbs):



Unfactored:			
Lateral:			
Dead			
Snow			
Wind	64		64
Axial:			
Dead	458		458
Snow	900		900
Factored:			
L->R	38		38
Load comb	#4		#4

Lumber Stud, S-P-F, Stud, 2x4 (1-1/2"x3-1/2")

Support: None

Spaced at 24.0" c/c; Total length: 8.0'; Volume = 0.3 cu.ft.

Pinned base; Load face = width(b); $K_e \times L_b: 1.0 \times 0.0 = 0.0$ ft; $K_e \times L_d: 1.0 \times 8.0 = 8.0$ ft; Repetitive factor: applied where permitted (refer to online help);

This section PASSES the design code check.

Analysis vs. Allowable Stress and Deflection using NDS 2018 :

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	$f_v = 11$	$F_v' = 216$	psi	$f_v/F_v' = 0.05$
Bending(+)	$f_b = 301$	$F_b' = 1366$	psi	$f_b/F_b' = 0.22$
Axial	$f_c = 259$	$F_c' = 409$	psi	$f_c/F_c' = 0.63$
Axial Bearing	$f_c = 259$	$F_c^* = 875$	psi	$f_c/F_c^* = 0.30$
Combined	(axial compression + side load bending)			Eq.3.9-3 = 0.55
Live Defl'n	$0.14 = L/697$	$0.80 = L/120$	in	0.17
Total Defl'n	$0.14 = L/697$	$0.80 = L/120$	in	0.17

Additional Data:

FACTORS:	F/E (psi)	CD	CM	Ct	CL/CP	CF	Cfu	Cr	Cfrt	Ci	LC#
Fv'	135	1.60	1.00	1.00	-	-	-	-	1.00	1.00	4
Fb'+	675	1.60	1.00	1.00	1.000	1.100	-	1.15	1.00	1.00	4
Fc'	725	1.15	1.00	1.00	0.467	1.050	-	-	1.00	1.00	2
Fc'comb	725	1.60	-	-	0.355	-	-	-	-	-	3
E'	1.2 million		1.00	1.00	-	-	-	-	1.00	1.00	4
Emin'	0.44 million		1.00	1.00	-	-	-	-	1.00	1.00	4
Fc*	725	1.15	1.00	1.00	-	1.050	-	-	1.00	1.00	2

CRITICAL LOAD COMBINATIONS:

Shear : LC #4 = 0.6D + 0.6W
 Bending(+): LC #4 = 0.6D + 0.6W
 Deflection: LC #4 = 0.6D + 0.6W (live)
 LC #4 = 0.6D + 0.6W (total)
 Axial : LC #2 = D + S
 Combined : LC #3 = D + 0.75(S + 0.6W);

D=dead S=snow W=wind

All LC's are listed in the Analysis output

Load combinations: ASD Basic from ASCE 7-16 2.4

CALCULATIONS:

V = 38 lbs; M(+) = 77 lbs-ft; P = 1358 lbs, $(1 - fc/FcE) = 0.55$

EI = 6.43e06 lb-in²

"Live" deflection is due to all non-dead loads (live, wind, snow...)

Total deflection = 1.50 permanent + "live"

Axial d governs, $l/b = 0.0$, $l/d = 27.4$

Design Notes:

1. Analysis and design are in accordance with the ICC International Building Code (IBC 2021) and the National Design Specification (NDS 2018), using Allowable Stress Design (ASD). Design values are from the NDS Supplement.
2. Please verify that the default deflection limits are appropriate for your application.



WoodWorks
SOFTWARE FOR WOOD DESIGN

COMPANY

PROJECT

Aug. 13, 2024 12:07

Wolff_New Stud.wwc


Design Check Calculation Sheet

WoodWorks Sizer 2023

Loads:

Load	Type	Distribution	Location [ft]		Magnitude		Unit
			Start	End	Start	End	
Load1	Dead	Axial UDL	(Ecc. = 0.00")		75		plf
Load2	Snow	Axial UDL	(Ecc. = 0.00")		150		plf
Load3	Wind	Full Area			20.00 (24.0")		psf
Self-weight	Dead	Axial UDL			4		plf

Reactions (lbs):



Unfactored:		
Lateral:		
Dead		
Snow		
Wind	160	160
Axial:		
Dead	158	158
Snow	300	300
Factored:		
L->R	96	96
Load comb	#4	#4

Lumber Stud, S-P-F, Stud, 2x4 (1-1/2"x3-1/2")

Support: None

Spaced at 24.0" c/c; Total length: 8.0'; Volume = 0.3 cu.ft.

Pinned base; Load face = width(b); $K_e \times L_b: 1.0 \times 0.0 = 0.0$ ft; $K_e \times L_d: 1.0 \times 8.0 = 8.0$ ft; Repetitive factor: applied where permitted (refer to online help);

This section PASSES the design code check.

Analysis vs. Allowable Stress and Deflection using NDS 2018 :

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	$f_v = 27$	$F_v' = 216$	psi	$f_v/F_v' = 0.13$
Bending (+)	$f_b = 752$	$F_b' = 1366$	psi	$f_b/F_b' = 0.55$
Axial	$f_c = 87$	$F_c' = 409$	psi	$f_c/F_c' = 0.21$
Axial Bearing	$f_c = 87$	$F_c^* = 875$	psi	$f_c/F_c^* = 0.10$
Combined	(axial compression + side load bending)			Eq.3.9-3 = 0.59
Live Defl'n	$0.34 = L/279$	$0.80 = L/120$	in	0.43
Total Defl'n	$0.34 = L/279$	$0.80 = L/120$	in	0.43

Additional Data:

FACTORS:	F/E (psi)	CD	CM	Ct	CL/CP	CF	Cfu	Cr	Cfrt	Ci	LC#
Fv'	135	1.60	1.00	1.00	-	-	-	-	1.00	1.00	4
Fb'+	675	1.60	1.00	1.00	1.000	1.100	-	1.15	1.00	1.00	4
Fc'	725	1.15	1.00	1.00	0.467	1.050	-	-	1.00	1.00	2
Fc'comb	725	1.60	-	-	0.355	-	-	-	-	-	5
E'	1.2 million		1.00	1.00	-	-	-	-	1.00	1.00	4
Emin'	0.44 million		1.00	1.00	-	-	-	-	1.00	1.00	4
Fc*	725	1.15	1.00	1.00	-	1.050	-	-	1.00	1.00	2

CRITICAL LOAD COMBINATIONS:

Shear : LC #4 = 0.6D + 0.6W
 Bending(+): LC #4 = 0.6D + 0.6W
 Deflection: LC #4 = 0.6D + 0.6W (live)
 LC #4 = 0.6D + 0.6W (total)
 Axial : LC #2 = D + S
 Combined : LC #5 = D + 0.6W;

D=dead S=snow W=wind

All LC's are listed in the Analysis output

Load combinations: ASD Basic from ASCE 7-16 2.4

CALCULATIONS:

V = 96 lbs; M(+) = 192 lbs-ft; P = 458 lbs, $(1 - fc/FcE) = 0.94$

EI = 6.43e06 lb-in²

"Live" deflection is due to all non-dead loads (live, wind, snow...)

Total deflection = 1.50 permanent + "live"

Axial d governs, $l/b = 0.0$, $l/d = 27.4$

Design Notes:

1. Analysis and design are in accordance with the ICC International Building Code (IBC 2021) and the National Design Specification (NDS 2018), using Allowable Stress Design (ASD). Design values are from the NDS Supplement.
2. Please verify that the default deflection limits are appropriate for your application.




Design Check Calculation Sheet
WoodWorks Sizer 2023

Loads:

Load	Type	Distribution	Pat-tern	Location [ft]		Magnitude		Unit
				Start	End	Start	End	
Load1	Dead	Full Area				15.00 (24.0")		psf
Load2	Snow	Full Area				30.00 (24.0")		psf
Load3	Wind	Full Area				20.00 (24.0")		psf
Self-weight	Dead	Full UDL				2.2		plf

Maximum Reactions (lbs), Bearing Capacities (lbs) and Bearing Lengths (in) :



Unfactored:			
Dead	170		170
Snow	318		318
Wind	212		212
Factored:			
Total	504		504
Bearing:			
F'theta	427		427
Capacity			
Joist	2243		2243
Support	2789		2789
Des ratio			
Joist	0.22		0.22
Support	0.18		0.18
Load comb	#3		#3
Length	3.50		3.50
Min req'd	0.79		0.79
Cb	1.00		1.00
Cb min	1.00		1.00
Cb support	-		-
Fcp sup	425		425

Bearing for wall supports is perpendicular-to-grain bearing on top plate. No stud design included.

Lumber-soft, S-P-F, No.1/No.2, 2x8 (1-1/2"x7-1/4")

Supports: All - Lumber Stud Wall, S-P-F Stud

Roof joist spaced at 24.0" c/c; Total length: 10.69'; Clear span(horz): 10.0'; Volume = 0.8 cu.ft.; Pitch: 1/12

Lateral support: top = continuous, bottom = at supports; Repetitive factor: applied where permitted (refer to online help);

This section PASSES the design code check.

Analysis vs. Allowable Stress and Deflection using NDS 2018 :

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	$f_v = 56$	$F_v' = 155$	psi	$f_v/F_v' = 0.36$
Bending(+)	$f_b = 1068$	$F_b' = 1389$	psi	$f_b/F_b' = 0.77$
Live Defl'n	$0.22 = L/550$	$0.51 = L/240$	in	0.44
Total Defl'n	$0.39 = L/311$	$0.67 = L/180$	in	0.58

Additional Data:

FACTORS:	F/E (psi)	CD	CM	Ct	CL	CF	Cfu	Cr	Cfrt	Ci	LC#
Fv'	135	1.15	1.00	1.00	-	-	-	-	1.00	1.00	2
Fb'+	875	1.15	1.00	1.00	1.000	1.200	-	1.15	1.00	1.00	2
Fcp'	425	-	1.00	1.00	-	-	-	-	1.00	1.00	-
E'	1.4 million	-	1.00	1.00	-	-	-	-	1.00	1.00	3
Emin'	0.51 million	-	1.00	1.00	-	-	-	-	1.00	1.00	3

CRITICAL LOAD COMBINATIONS:

Shear : LC #2 = D + S
 Bending(+): LC #2 = D + S
 Deflection: LC #3 = D + 0.75(S + 0.6W) (live)
 LC #3 = D + 0.75(S + 0.6W) (total)
 Bearing : Support 1 - LC #3 = D + 0.75(S + 0.6W)
 Support 2 - LC #3 = D + 0.75(S + 0.6W)

D=dead S=snow W=wind

All LC's are listed in the Analysis output

Load Patterns: s=S/2, X=L+S or L+Lr, _=no pattern load in this span

Load combinations: ASD Basic from ASCE 7-16 2.4

CALCULATIONS:

V max = 463, V design = 405 (NDS 3.4.3.1(a)) lbs; M(+) = 1169 lbs-ft

EI = 66.69e06 lb-in²

"Live" deflection is due to all non-dead loads (live, wind, snow...)

Total deflection = 1.50 permanent + "live"

Bearing: Allowable bearing at an angle F'theta calculated for each support
 as per NDS 3.10.3

Design Notes:

1. Analysis and design are in accordance with the ICC International Building Code (IBC 2021) and the National Design Specification (NDS 2018), using Allowable Stress Design (ASD). Design values are from the NDS Supplement.
2. Please verify that the default deflection limits are appropriate for your application.
3. Sawn lumber bending members shall be laterally supported according to the provisions of NDS Clause 4.4.1.
4. SLOPED BEAMS: level bearing is required for all sloped beams.




Design Check Calculation Sheet
WoodWorks Sizer 2023

Loads:

Load	Type	Distribution	Pat-tern	Location [ft]		Magnitude		Unit
				Start	End	Start	End	
Load1	Dead	Full Area				15.00 (24.0")		psf
Load2	Snow	Full Area				30.00 (24.0")		psf
Load3	Wind	Full Area				20.00 (24.0")		psf
Self-weight	Dead	Full UDL				2.2		plf

Maximum Reactions (lbs), Bearing Capacities (lbs) and Bearing Lengths (in) :



Unfactored:			
Dead	172		172
Snow	317		318
Wind	212		212
Factored:			
Total	505		505
Bearing:			
F'theta	434		434
Capacity			
Joist	2279		2279
Support	2789		2789
Des ratio			
Joist	0.22		0.22
Support	0.18		0.18
Load comb	#3		#3
Length	3.50		3.50
Min req'd	0.78		0.78
Cb	1.00		1.00
Cb min	1.00		1.00
Cb support	-		-
Fcp sup	425		425

Bearing for wall supports is perpendicular-to-grain bearing on top plate. No stud design included.

Lumber-soft, S-P-F, No.1/No.2, 2x8 (1-1/2"x7-1/4")

Supports: All - Lumber Stud Wall, S-P-F Stud

Roof joist spaced at 24.0" c/c; Total length: 10.81'; Clear span(horz): 10.0'; Volume = 0.8 cu.ft.; Pitch: 2/12

Lateral support: top = continuous, bottom = at supports; Repetitive factor: applied where permitted (refer to online help);

This section PASSES the design code check.

Analysis vs. Allowable Stress and Deflection using NDS 2018 :

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	$f_v = 56$	$F_v' = 155$	psi	$f_v/F_v' = 0.36$
Bending(+)	$f_b = 1071$	$F_b' = 1389$	psi	$f_b/F_b' = 0.77$
Live Defl'n	$0.23 = L/541$	$0.51 = L/240$	in	0.44
Total Defl'n	$0.40 = L/305$	$0.68 = L/180$	in	0.59

Additional Data:

FACTORS:	F/E (psi)	CD	CM	Ct	CL	CF	Cfu	Cr	Cfrt	Ci	LC#
Fv'	135	1.15	1.00	1.00	-	-	-	-	1.00	1.00	2
Fb'+	875	1.15	1.00	1.00	1.000	1.200	-	1.15	1.00	1.00	2
Fcp'	425	-	1.00	1.00	-	-	-	-	1.00	1.00	-
E'	1.4 million	-	1.00	1.00	-	-	-	-	1.00	1.00	3
Emin'	0.51 million	-	1.00	1.00	-	-	-	-	1.00	1.00	3

CRITICAL LOAD COMBINATIONS:

Shear : LC #2 = D + S
 Bending(+): LC #2 = D + S
 Deflection: LC #3 = D + 0.75(S + 0.6W) (live)
 LC #3 = D + 0.75(S + 0.6W) (total)
 Bearing : Support 1 - LC #3 = D + 0.75(S + 0.6W)
 Support 2 - LC #3 = D + 0.75(S + 0.6W)

D=dead S=snow W=wind

All LC's are listed in the Analysis output

Load Patterns: s=S/2, X=L+S or L+Lr, _=no pattern load in this span

Load combinations: ASD Basic from ASCE 7-16 2.4

CALCULATIONS:

V max = 460, V design = 402 (NDS 3.4.3.1(a)) lbs; M(+) = 1173 lbs-ft

EI = 66.69e06 lb-in²

"Live" deflection is due to all non-dead loads (live, wind, snow...)

Total deflection = 1.50 permanent + "live"

Bearing: Allowable bearing at an angle F'theta calculated for each support
 as per NDS 3.10.3

Design Notes:

1. Analysis and design are in accordance with the ICC International Building Code (IBC 2021) and the National Design Specification (NDS 2018), using Allowable Stress Design (ASD). Design values are from the NDS Supplement.
2. Please verify that the default deflection limits are appropriate for your application.
3. Sawn lumber bending members shall be laterally supported according to the provisions of NDS Clause 4.4.1.
4. SLOPED BEAMS: level bearing is required for all sloped beams.

B.3 Fastener Schedule

MINIMUM FASTENER SCHEDULE TABLE

Other interior and exterior panel products and finishes installed per manufacturer requirements.

For engineered connectors, use manufacturer's specified fasteners.

Description of Building Materials/Connection	Number and Type of Fastener ^{1 2 3}
Floor Framing	
Joist to joist, face nailed over support	2-12d
Joist to sill or girder, toe nail	2-16d, 3-8d
Band or rim joist to joist, end nail	3-16d
Band or rim joist to sill or top plate	2-16d at 16" o.c.
Bridging to joist, toe nail each end	2-8d
Built-up girder and beams, top loaded	10d at 32" o.c. at top and bottom and staggered and two at ends and at each splice
Built-up girder and beams, side-loaded	16d at 16" o.c. at top and bottom and staggered and two at ends and at each splice
Ledger strip to beam, face nail	3-16d each joist
Joist on ledger to beam, toe nail	3-8d
Wall Framing	
Sole plate to joist or blocking, face nail	16d at 16" o.c.
Top or sole plate to stud, end nail	2-16d
Stud to sole plate, toe nail	4-8d or 3-16d
Doubled studs, face nail	16d at 24" o.c.
Doubled top plates, face nail	16d at 16" o.c.
Top plates, laps and intersections, face nail	2-16d
Continuous header, two pieces	16d at 16" o.c. along each edge
Continuous header to stud, toe nail	4-8d
1" corner brace to each stud and plate, face nail	2-8d or 2 staples, 1 3/4"
Built-up corner studs	16d at 30" o.c., 16d at 24" o.c.
Roof/Ceiling Framing	
Ceiling joists to plate, toe nail	2-16d, 3-8d
Ceiling joist, laps over partitions, face nail	3-16d
Ceiling joist to parallel rafters, face nail	3-16d
Rafter to plate, toe nail (maximum 6 rafter span, engineered connector for longer)	2-16d, 3-8d
Roof rafters to ridge, valley or hip rafters, toe nail	4-16d
Roof rafters to ridge, valley or hip rafters, face nail	3-16d
Collar ties to rafters, face nail	3-8d
Boards and planks	
1" x 6" subfloor or less to each joist, face nail	2-8d or 2 staples, 1 3/4"
Wider than 1" x 6" subfloor toe to each joist, face nail	3-8d or 4 staples 1 3/4"
2" subfloor to joist or girder, blind and face nail	2-16d
1" x 6" roof or wall sheathing to each bearing, face nail	2-8d or 2 staples, 1 3/4"
1" x 8" roof or wall sheathing to each bearing, face nail	2-8d or 3 staples, 1 3/4"
Wider than 1" x 8" roof sheathing to each bearing, face nail	3-8d or 4 staples, 1 3/4"
2" planks	2-16d at each bearing

Panel Sheathing

Material	Fastener	Spacing of Fastener	
		Edges	Intermediate Supports
Engineered wood panel for sub-floor and roof sheathing and wall corner wind bracing to framing			
$5/16''$ to $1/2''$	6d common or deformed nail or staple, $1\frac{1}{2}''$	6"	12" ⁴
$5/8''$ to $3/4''$	8d smooth or common, 6d deformed nail, or staple, 14 ga. $1\frac{3}{4}''$	6"	12" ⁴
$7/8''$ to 1"	8d common or deformed nail	6"	12"
$1\frac{1}{8}''$ to $1\frac{1}{4}''$	10d smooth or common, or 8d deformed nail	6"	12"
Combination subfloor/ underlayment to framing			
$3/4''$ or less	6d deformed or 8d smooth or common nail	6"	12"
$7/8''$ to 1"	8d smooth, common or deformed nail	6"	12"
$1\frac{1}{8}''$ to $1\frac{1}{4}''$	10d smooth or common or 8d deformed nail	6"	12"
Wood panel siding to framing			
$1/2''$ or less	6d corrosion-resistant siding and casing nails	6"	12"
$5/8''$	8d corrosion-resistant siding and casing nails	6"	12"
$1/2''$ structural cellulosic fiberboard sheathing	$1\frac{1}{2}''$ galvanized roofing nail; 8d common nail; staple 16 ga., $1\frac{1}{2}''$ long	3"	6"
$25/32''$ structural cellulosic fiberboard sheathing	$1\frac{3}{4}''$ galvanized roofing nail; 8d common nail; staple 16 ga., $1\frac{3}{4}''$ long	3"	6"
$1/2''$ gypsum sheathing ⁵	$1\frac{1}{2}''$ galvanized roofing nail; 6d common nail; staple galvanized $1\frac{1}{2}''$ long; $1\frac{1}{4}''$ screws, Type W or S	4"	8"
$5/8''$ gypsum sheathing ⁵	$1\frac{3}{4}''$ galvanized roofing nail; 8d common nail; staple galvanized $1\frac{5}{8}''$ long; $1\frac{5}{8}''$ screws, Type W or S	4"	8"

¹ All nails are smooth-common, box or deformed shank except where otherwise stated.

² Nail is a general description and may be T-head, modified round head or round head.

³ Staples are 16-gauge wire, unless otherwise noted, and have a minimum $7/16''$ o.d. crown width.

⁴ Staples shall be spaced at not more than 10" o.c. at intermediate supports for floors.

⁵ Apply vertically 4' x 8' or 4' x 9' panels.

Wolff Residence - Garage Addition

7528 N Links Way
Fox Point, WI
53217

Architect :
Brian Wolff
7528 N Links Way
Fox Point, WI



Wolff Residence - Garage Addition

Design Documents for Village Approval

DRAWING INDEX		
REV	NUMBER	SHEET NAME
	A000	SITE PLAN
	A100	DEMOLITION PLAN/ELEV.
	A200	FOUNDATION PLAN
	A201	FRAMING PLAN
	A202	RAFTER PLAN
	A300	SECTION
	A400	ELEVATION
	A401	ELEVATION
	A500	DETAILS
	A600	PERSPECTIVE




Date: August 21, 2024

Village Planning Approval

Wolff Residence - Garage Addition

7528 N Links Way
Fox Point, WI
53217

Architect :
Brian Wolff
7528 N Links Way
Fox Point, WI



NON DWELLING LAND USE

PARCEL AREA	13,329 SF
EXISTING DETACHED GARAGE	400 SF
GARAGE ADDITION	200 SF
NON DWELLING LAND USE =	4.5%



Site Plan

Design Documents for Village Approval



Date: August 21, 2024

Village Planning Approval

Wolff Residence - Garage Addition

7528 N Links Way
Fox Point, WI
53217

Architect :
Brian Wolff
7528 N Links Way
Fox Point, WI



2 Existing East Elevation - Demolition
SCALE: 1/4" = 1'-0"

1 DEMOLITION PLAN
SCALE: 3/8" = 1'-0"


Demolition
Design Documents
for Village
Approval

Date: August 21, 2024
Village Planning Approval

Wolff Residence - Garage Addition

7528 N Links Way
Fox Point, WI
53217

Architect :
Brian Wolff
7528 N Links Way
Fox Point, WI



Foundation Plan

Design Documents for Village Approval


Date: August 21, 2024

Village Planning Approval

Wolff Residence - Garage Addition

7528 N Links Way
Fox Point, WI
53217

Architect :
Brian Wolff
7528 N Links Way
Fox Point, WI



General Notes:
Fasteners Scheduled According to Minimum
Fastener Schedule Table of Wisconsin UDC
Appendix B.3

Framing Plan

Design Documents for Village Approval

Date: August 21, 2024

Village Planning Approval

1
A300

1

FRAMING PLAN - EXTERIOR WALL

SCALE: 3/8" = 1'-0"

A201

Wolff Residence - Garage Addition

7528 N Links Way
Fox Point, WI
53217

Architect :
Brian Wolff
7528 N Links Way
Fox Point, WI



General Notes:
Fasteners Scheduled According to Minimum
Fastener Schedule Table of Wisconsin UDC
Appendix B.3

Framing Plan - Roof
Design Documents
for Village
Approval

Date: August 21, 2024

Village Planning Approval

1

FRAMING PLAN - RAFTER


SCALE: 3/8" = 1'-0"

A202


Wolff Residence - Garage Addition

7528 N Links Way
Fox Point, WI
53217

Architect :
Brian Wolff
7528 N Links Way
Fox Point, WI



1 SOUTH ELEVATION
SCALE: 1/4" = 1'-0"



2 NORTH ELEVATION
SCALE: 1/4" = 1'-0"

Elevation

Design Documents for Village Approval


Date: August 21, 2024

Village Planning Approval

Wolff Residence - Garage Addition

7528 N Links Way
Fox Point, WI
53217

Architect :
Brian Wolff
7528 N Links Way
Fox Point, WI



1 EAST ELEVATION
SCALE: 1/4" = 1'-0"

Elevation

Design Documents
for Village
Approval


Date: August 21, 2024

Village Planning Approval

Wolff Residence - Garage Addition

7528 N Links Way
Fox Point, WI
53217

Architect :
Brian Wolff
7528 N Links Way
Fox Point, WI



1 SECTION
SCALE: 3/8" = 1'-0"

Section
Design Documents
for Village
Approval


Date: August 21, 2024

Village Planning Approval


Wolff Residence - Garage Addition

7528 N Links Way
Fox Point, WI
53217


Architect :
Brian Wolff
7528 N Links Way
Fox Point, WI




1 SOFFIT @ EXTERIOR DOOR
SCALE: 1-1/2" = 1'-0"



2 ASPHALT TO STEEL ROOF TRANSITION
SCALE: 1-1/2" = 1'-0"



3 North Elevation
SCALE: 1-1/2" = 1'-0"



4 Thickened Slab
SCALE: 1-1/2" = 1'-0"

Details
Design Documents
for Village
Approval

Date: August 21, 2024

Village Planning Approval

Wolff Residence - Garage Addition

7528 N Links Way
Fox Point, WI
53217

Architect :
Brian Wolff
7528 N Links Way
Fox Point, WI



1

PERSPECTIVE FACING REAR ENTRY
SCALE: NOT TO SCALE

Perspective

Design Documents
for Village
Approval

Date: August 21, 2024

Village Planning Approval



VILLAGE OF FOX POINT
 7200 N Santa Monica Blvd
 Fox Point, WI 53217
 (414) 247-6622
 www.villageoffoxpoint.com

Permit Number:

B-

OFFICE USE ONLY
Issued Date
Zoning

BUILDING PERMIT

Job Address 7402 N Crossway Road	Building Type: Residential <input checked="" type="checkbox"/> Commercial <input type="checkbox"/>
Description of Work Replace existing window - raising sill approximately 14" to match height of 2nd kitchen window. Adding a new sill 2x4 or 2x6 with sleeper studs supporting sill 16" on center. No alteration to the header. Will add new OSV to the exterior of newly raised opening followed by a water barrier then LP	
Estimated Cost of Project \$ 1,800.00 Smart Side with trim and caulk	

Owner/Occupant	
Business Name B	Contact Name Lisa Friedel
Address 7402 N Crossway Rd	City/State/Zip Fox Point WI 53217
Phone 262-212-0597	Email Ohifloss@gmail.com

****Cautionary Statement required when homeowner is applying for permit****

Contractor	
Company Name Infinity Exteriors	Contact Name Zac Drew
Address 16600 W. Cleveland Ave.	City/State/Zip New Berlin WI 53151
Phone 262-221-2269	Email zac@infinityroofing.com
Dwelling Contractor #	Dwelling Contractor Qualifier #

Square Footage Under Construction				
1st Floor	2nd Floor	Basement	Addition	Garage

Description	Rate	Amount
Project - Per \$1,000 of estimated cost	\$10.00	10.00
Building Board	\$75.00	75.00
Footing early start - \$230.00 one and two family; \$305.00 commercial		
Plan Review - \$275.00 one and two family; New Single Family Construction \$330.00 plus \$30.00/unit commercial		
State Seal	\$75.00	
Razing, Interior Demolition \$925.00 max/bld	\$95.00 minimum plus	\$0.13/sqft
Moving buildings	\$250.00 plus	\$0.13/sqft
Fuel tanks - Per 1,000 gallons	\$25.00	
Re-inspection	\$100.00	
Work started without permit	Double	
	Minimum Fee	\$70.00
Payable to: Village of Fox Point	Total Permit Fee	\$ 145.00

Applicant Signature

[Handwritten Signature]

Date

8-28-24

ISSUED PERMITS are available on the Village website under PERMITS & LICENSES

Receipt No: 3.119735

Sep 2, 2024

7402 N CROSSWAY


Previous Balance:	.00
LICENSES & PERMITS	
BUILDING PERMIT	70.00
24-44460	
BUILDING PERMIT	
LICENSES & PERMITS	
BUILDING PLANS - FILING	75.00
FEE	
24-44440	
BUILDING PLANS-FILING FEE	

Total:	-----	145.00
--------	-------	--------

CHECK	=====	
Check No: 2613		145.00
Total Applied:		145.00

Change Tendered:	-----	.00
------------------	-------	-----

08/30/2024 8:03 AM



Both Kitchen windows will have the same sill height

7402 N Crossway Road





VILLAGE OF FOX POINT
 7200 N Santa Monica Blvd
 Fox Point, WI 53217
 (414) 247-6622
 www.villageoffoxpoint.com

Permit Number:

B- _____

OFFICE USE ONLY	
Issued Date	
Zoning	B, 55-

BUILDING PERMIT

Job Address 7630 N BOYD WAY	Building Type: Residential <input checked="" type="checkbox"/> Commercial <input type="checkbox"/>
Description of Work SECOND STORY REAR ADDITION	
Estimated Cost of Project \$	

Owner/Occupant	
Business Name LAURIE BERGUM	Contact Name LAURIE BERGUM
Address 7630 N BOYD WAY	City/State/Zip FOX POINT, WI 53217
Phone 608-669-4923	Email Keith@kcbbuildings.com

****Cautionary Statement required when homeowner is applying for permit****

Contractor	
Company Name	Contact Name
Address	City/State/Zip
Phone	Email
Dwelling Contractor #	Dwelling Contractor Qualifier #

Square Footage Under Construction				
1 st Floor	2 nd Floor	Basement	Addition	Garage
	225			

Description	Rate	Amount
Project - Per \$1,000 of estimated cost	\$10.00	
Building Board	\$75.00	75-
Footing early start - \$230.00 one and two family; \$305.00 commercial		
Plan Review - \$275.00 one and two family; New Single Family Construction \$330.00 plus \$30.00/unit commercial		
State Seal	\$75.00	
Razing, Interior Demolition \$925.00 max/bld \$95.00 minimum plus	\$0.13/sqft	
Moving buildings \$250.00 plus	\$0.13/sqft	
Fuel tanks - Per 1,000 gallons	\$25.00	
Re-inspection	\$100.00	
Work started without permit	Double	
	Minimum Fee	\$70.00
Payable to: Village of Fox Point	Total Permit Fee	\$ 75-

Applicant Signature
 Rev 01/22

Keith Barnes

Date

8/30/2024

ISSUED PERMITS are available on the Village website under PERMITS & LICENSES

Receipt No: 3.119737

Sep 2, 2024

7630 N BOYD

Previous Balance:	.00
LICENSES & PERMITS	
BUILDING PLANS - FILING FEE	75.00
24-44440	
BUILDING PLANS-FILING FEE	

Total:	----- 75.00 =====
--------	-------------------------

CHECK	
Check No: 957	75.00
Total Applied:	75.00

Change Tendered:	----- .00 =====
------------------	-----------------------

Duplicate Copy
08/30/2024 9:51 AM

REGIONAL CONSULTING ENGINEERS, INC.

PROFESSIONAL ENGINEERS AND SURVEYORS
MILWAUKEE, WISCONSIN

4842 NO. 88TH ST.



PHONE 464-4638

PLAT OF SURVEY

DESCRIPTION: All that part of the NW 1/4 of Section 16, Township 8 North, Range 22 East in the Village of Fox Point, Milwaukee County, Wisconsin described as follows: Commencing at a point in the east and west 1/4 line, 1093 feet, N 89° 56' 00" W of the center of the said Section 16; running thence N 00° 14' 30" E, 460.00 feet to the place of beginning of the lands to be described; thence S 89° 56' 00" E, 210.00 feet; thence N 00° 14' 30" E, 100.00 feet; thence N 89° 56' 00" W, 210.00 feet to a point in the center of a reservation for highway purposes 50 feet in width; thence S 00° 14' 30" W, along the centerline of said reservation for highway purposes, 100.00 feet to the place of beginning. Excepting therefrom the westerly 25 feet for highway purposes.

OWNERS: Daniel and Holly Morse, 7630 North Boyd Way, Fox Point

This is not the original copy if surveyor's signature is not in red



STATE OF WISCONSIN }
COUNTY OF MILWAUKEE } SS.

I HAVE SURVEYED THE ABOVE-DESCRIBED PROPERTY AND THE ABOVE MAP IS A TRUE REPRESENTATION THEREOF AND SHOWS THE SIZE AND LOCATION OF THE PROPERTY, ITS EXTERIOR BOUNDARIES, THE LOCATION AND DIMENSIONS OF ALL VISIBLE STRUCTURES THEREON, FENCES, APPARENT EASEMENTS AND ROADWAYS AND VISIBLE ENCROACHMENTS, IF ANY.

THIS SURVEY IS MADE FOR THE EXCLUSIVE USE OF THE PRESENT OWNERS OF THE PROPERTY, AND ALSO THOSE WHO PURCHASE, MORTGAGE, OR GUARANTEE THE TITLE THERETO WITHIN ONE (1) YEAR FROM DATE HEREOF; AND AS TO THEM I CERTIFY THE ACCURACY OF SAID SURVEY AND MAP.

NOTE: AN AGREEMENT EXISTS BETWEEN REGIONAL CONSULTING ENGINEERS, INC. AND THE LENDING INSTITUTION TO OMIT THE RESETING OF ANY MISSING LOT CORNER PIPES ON THIS SURVEY UNLESS SPECIFICALLY REQUESTED AT THE TIME OF SURVEY ORDER PLACEMENT.

DATED THIS 4th DAY OF March 19 88

Robert R. Koff
SURVEYOR

JOB NO _____



VILLAGE OF FOX POINT
 7200 N Santa Monica Blvd
 Fox Point, WI 53217
 (414) 247-6622
 www.villageoffoxpoint.com

Permit Number:

B-_____

OFFICE USE ONLY	
Issued Date	
Zoning	C, 60

BUILDING PERMIT

Job Address 8025 N Whitney Road	Building Type: Residential <input checked="" type="checkbox"/> Commercial <input type="checkbox"/>
Description of Work	
Building a deck off of the rear of the home.	
**Open Area Calculation - Zone C - to be less than 8000-10500 sq ft	
Open Area Sq Ft Approx = 1,955	
Estimated Cost of Project \$ 30,000	

Owner/Occupant	
Business Name	Contact Name Linda Tredupp
Address 8025 N Whitney Road	City/State/Zip Fox Point, WI 53217
Phone 414-719-2160	Email ltredupp@wi.rr.com

****Cautionary Statement required when homeowner is applying for permit****

Contractor	
Company Name Lakeside Deck Builders	Contact Name Jason Rose
Address 210 N River Road	City/State/Zip West Bend, WI 53095
Phone 262-716-6036	Email lakesidecontracting.anny@gmail.com
Dwelling Contractor # 051500021	Dwelling Contractor Qualifier # 051500001

Square Footage Under Construction				
1 st Floor	2 nd Floor	Basement	Addition 368	Garage

Description	Rate	Amount
Project - Per \$1,000 of estimated cost	\$10.00	
Building Board	\$75.00	
Footing early start - \$230.00 one and two family; \$305.00 commercial		
Plan Review - \$275.00 one and two family; New Single Family Construction \$330.00 plus \$30.00/unit commercial		
State Seal	\$75.00	
Razing, Interior Demolition \$925.00 max/bld	\$95.00 minimum plus	\$0.13/sqft
Moving buildings	\$250.00 plus	\$0.13/sqft
Fuel tanks - Per 1,000 gallons		\$25.00
Re-inspection		\$100.00
Work started without permit		Double
	Minimum Fee	\$70.00
Payable to: Village of Fox Point	Total Permit Fee	\$

Applicant Signature Anny L. Mayer **Date** 8/26/2024

Rev 01/22

ISSUED PERMITS are available on the Village website under PERMITS & LICENSES

Receipt No: 18.000045

Aug 26, 2024

Jason Rose

LICENSES & PERMITS

Online Payment 375.00



Total: 375.00

ONLINE - CREDIT CARD 375.00

Total Applied: 375.00

Change Tendered: .00

08/27/24 07:49AM




Known as 8025 Whitney Road, in the Village of Fox Point, Wisconsin
 Lots 10 and 11 in Block 4 in FOX POINT GARDENS, being a Subdivision of a part
 of the S W 1/4 of Section 9, T 8 N, R 22 E, in the Village of Fox Point,
 Milwaukee County, Wisconsin

MAY 21, 1974

ALICE D KING-OWNER

SURVEY NO. 134763-S



SCALE: 1" = 30'

MAY 21, 1974

I Certify that I have surveyed the above described property (Property), and the above map is a true repre-